

**EARTHWORK ANALYSIS**

STRUCTURE NUMBER	TREE REMOVAL	EARTH EXCAVATION	EARTH EXCAVATION EMBANKMENT ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	UNITS	CU YD	CU YD	CU YD	CU YD
061-0027		10.68	8.01	262.10	-254.09
061-0046		14.03	10.52	387.92	-377.40
061-0017		60.79	45.59	585.30	-539.70
061-0045		51.03	38.27	493.74	-455.47
061-0028		44.49	33.37	259.83	-226.46
061-0044	6	6.79	5.09	275.27	-270.18
061-0026		68.70	51.53	584.75	-533.22
061-0042		59.61	44.71	354.88	-310.17
061-0043		47.34	35.50	319.86	-284.36
061-0025		52.67	39.50	288.91	-249.41
061-0057		117.65	88.24	219.39	-131.15
061-0010		5.69	4.27	653.08	-648.81
061-0058		95.76	71.82	209.77	-137.95
061-0061		10.39	7.79	344.27	-336.48
061-0064		110.04	82.53	293.67	-211.14
<b>TOTAL</b>	<b>6</b>	<b>755.65</b>	<b>566.74</b>	<b>5,532.72</b>	<b>-4,966.0</b>
<b>USE</b>	<b>6</b>	<b>755</b>	<b>565</b>	<b>5535</b>	<b>-4970</b>