SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		0021 90% FED 10% STATE	———	———
20200500	EARTH EXCAVATION (WIDENING)	CU YD	562.5	562.5		
25000210	SEEDING, CLASS 2A	ACRE	1.25	1.25		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	112.5	112.5		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	112.5	112.5		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	112.5	112.5		
25100115	MULCH, METHOD 2	ACRE	1.25	1.25		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	125	125		
28000400	PERIMETER EROSION BARRIER	FOOT	200	200		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	2400	2400		
64200105	SHOULDER RUMBLE STRIPS	FOOT	7200	7200		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	15	15		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		———	———	———

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED - ___	REVISED - ___
		DRAWN - ___	REVISED - ___
	PLOT SCALE = $SCALE$	CHECKED - ___	REVISED - ___
	PLOT DATE = $DATE$	DATE - _____	REVISED - ___

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: _____ | SHEET NO. __ OF ___ SHEETS | STA. _____ TO STA. _____

F.A.P RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
805	3-1	CLINTON	8	3

CONTRACT NO. 76E31

FED. ROAD DIST. NO. _ | ILLINOIS | FED. AID PROJECT