

STATION	END AREA		DIST FEET	EARTHWORK VOL			EARTHWORK BALANCE WASTE(+)/SHORTAGE(-) CU YD
	CUT	FILL		UNADJUSTED	ADJUSTED	FILL	
	SQ FT	SQ FT		CU YD	CU YD	CU YD	
407+00.00	4.00	1.00	200	29.6	22.2	8.9	13.3
409+00.00	4.00	1.40	200	29.6	22.2	7.1	15.1
411+00.00	4.00	0.53	200	29.6	22.2	5.7	16.5
413+00.00	4.00	1.00	200	29.6	22.2	9.3	12.9
415+00.00	4.00	1.50	200	29.6	22.2	10.0	12.2
417+00.00	4.00	1.20	200	29.6	22.2	8.1	14.1
419+00.00	4.00	0.98	200	29.6	22.2	7.3	14.9
421+00.00	4.00	1.00	200	29.6	22.2	5.6	16.6
423+00.00	4.00	0.50	200	29.6	22.2	3.0	19.2
425+00.00	4.00	0.30	200	29.6	22.2	3.2	19.0
427+00.00	4.00	0.56	200	29.6	22.2	5.2	17.0
429+00.00	4.00	0.85	200	29.6	22.2	4.4	17.8
431+00.00	4.00	1.00	400	59.3	44.5	11.7	32.8
433+00.00	4.00	0.35	200	29.6	22.2	3.4	18.8
435+00.00	4.00	0.58	200	29.6	22.2	5.9	16.3
437+00.00	4.00	1.00	200	29.6	22.2	5.0	17.2
439+00.00	4.00	0.34	200	29.6	22.2	3.3	18.9
441+00.00	4.00	0.56	200	29.6	22.2	5.0	17.2
443+00.00	4.00	0.79	200	29.6	22.2	5.0	17.2
445+00.00	4.00	0.56	200	29.6	22.2	3.4	18.8
447+00.00	4.00	0.35	200	29.6	22.2	5.0	17.2
449+00.00	4.00	1.00	200	29.6	22.2	7.4	14.8
451+00.00	4.00	1.00	200	14.8	11.1	3.7	7.4
453+00.00	0.00	0.00					
SUB-TOTAL				695.7	521.8	136.6	385.2

SHOULDER SCHEDULE						
STA.	TO	STA.	SIDE	LENGTH (FOOT)	HMA SHOULDERS 8" (SQ YD)	SHOULDER RUMBLE STRIP (FOOT)
407+00	TO	451+00	L/R	4400	2933.3	8800
TOTAL:					2933.3	8800

SEEDING									
STA.	TO	STA.	SIDE (L/T/R)	SEEDING CLASS 2 (ACRE)	NITROGEN FERTILIZER (POUND)	PHOSPHORUS FERTILIZER (POUND)	POTASSIUM NUTRIENT (POUND)	MULCH METHOD (ACRE)	PERIMETER EROSION BARRIER (FOOT)
407+00	TO	451+00	L	0.805	72.75	72.75	72.75	0.805	
407+00	TO	451+00	R	0.805	72.75	72.75	72.75	0.805	
409+00	TO	409+50	L/R						100
449+50	TO	450+00	L/R						100
TOTAL:				1.61	145.5	145.5	145.5	1.61	200

FILE NAME = #FILE#	USER NAME = #USER#	DESIGNED - ---	REVISED - ---	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES		F.A.P. RTE. 793	SECTION 112-1	COUNTY 8080	TOTAL SHEETS 8	SHEET NO. 5	
	PLOT SCALE = #SCALE#	DRAWN - ---	REVISED - ---		SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 78E32				
	PLOT DATE = #DATE#	CHECKED - ---	REVISED - ---		FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT							
		DATE - -----	REVISED - ---									