

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		50% FED. 50% STATE URBAN 0021			CODE NO	ITEM	UNIT				
25000210	SEEDING, CLASS 2A	ACRE	1.2	1.2									
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108	108									
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108	108									
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108	108									
25100105	MULCH, METHOD 1	ACRE	1.2	1.2									
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120	120									
28000500	INLET AND PIPE PROTECTION	EACH	12	12									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	12	12									
67100100	MOBILIZATION	L SUM	1	1									
70100420	TRAFFIC CONTROL AND PROTECTION, STANDARD 701411	EACH	2	2									
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1									
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1									
80300100	LOCATING UNDERGROUND CABLE	FOOT	19800	19800									
81300835	JUNCTION BOX, STAINLESS STEEL, ATTACHED TO STRUCTURE, 18" X 18" X 10"	EACH	2	2									
81400700	HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	26	26									
81400720	DOUBLE HANDHOLE, PORTLAND CEMENT CONCRETE	EACH	6	6									
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	19500	19500									
87100110	FIBER OPTIC CABLE IN CONDUIT, NO. 62.5/125, 6F	FOOT	7500	7500									
87300925	ELECTRIC CABLE IN CONDUIT, TRACER, NO.14 1C	FOOT	20,700	20,700									
87900100	DRILL EXISTING FOUNDATION	EACH	1	1									
87900200	DRILL EXISTING HANDHOLE	EACH	4	4									
X0322227	CLOSED CIRCUIT TELEVISION CAMERA SYSTEM	EACH	4	4									
X0325073	MODIFY EXISTING CONTROLLER CABINET TYPE B	EACH	4	4									
X0325075	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., FIBERGLASS BULLET RESISTANT	FOOT	60	60									
X0325076	WIDE AREA NETWORK	L SUM	1	1									
X0325077	FIBER OPTIC UTILITY MARKER	EACH	115	115									
X0325483	SFP-GE-L SFP MODULE	EACH	9	9									
X0326412	3000 LAYER 2 SWITCH	EACH	4	4									
X8100065	CONDUIT IN TRENCH, 4" DIA., PVC TYPE C	FOOT	19500	19500									
X0327096	ETHERNET MODEM	EACH	4	4									
X8110128	CONDUIT ATTACHED TO STRUCTURE, 4" DIA., PVC TYPE C	FOOT	80	80									
X8102020	CONDUIT PUSHED, 4" DIA., PVC SCHEDULE 80	FOOT	650	650									
X8710075	FIBER OPTIC CABLE IN CONDUIT, 72 COND. S.M. F.O.	FOOT	22700	22700									
X8950212	MODIFY EXISTING CONTROLLER CABINET, SPECIAL	EACH	2	2									