

PAVEMENT MARKING SCHEDULE										
LOCATION	PAINT PAVEMENT MARKING PERMANENT				SHORT TERM PAVEMENT MARKING	WORK ZONE PAVEMENT MARKING REMOVAL	PAVEMENT REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL
	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE	4" SINGLE WHITE EDGE LINE	4" SKIPPED DASHED YELLOW CENTERLINE						
	70300220	70300220	78001110	78001110						
	FOOT	FOOT	FOOT	FOOT	70300100	70301000	78300100	78100100	78100105	78300200
					FOOT	SQ FT	SQ FT	EACH	EACH	EACH
FAP 328 US RTE 45										
STAGE I										
LT. STA. 806+25 TO RT. STA. 810+50							142			
CL. STA. 804+40 TO CL. STA. 806+60							34			
RT. STA. 806+25 TO LT. STA. 810+50							142			
STAGE II										
LT. STA. 804+55.00 TO LT. STA. 812+70.00	815		815			269				
CL. STA. 804+55.00 TO CL. STA. 812+70.00		204		204	222	140		9	3	11
RT. STA. 804+55.00 TO RT. STA. 812+70.00	815		815			269				
SUBTOTAL	1630	204	1630	204	222	678	318	9	3	11
TOTAL		1834		1834	222	678	318	9	3	11

EROSION CONTROL SCHEDULE		
LOCATION	EROSION CONTROL BLANKET	PERIMETER EROSION BARRIER
	25100630 SQ YD	28000400 FOOT
FAP 328 US 45		
RT. STA. 804+55 TO RT. STA. 807+00		252
RT. STA. 804+55 TO RT. STA. 808+15	840	
LT. STA. 804+55 TO LT. STA. 808+15	389	369
RT. STA. 808+80 TO RT. STA. 812+70	671	427
LT. STA. 808+80 TO LT. STA. 812+70	659	374
TOTAL	2559	1422

TEMPORARY DITCH CHECK SCHEDULE	
LOCATION	FOOT
FAP 328 US 45	
RT. STA. 807+50	11
RT. STA. 808+15	11
TOTAL	22

EARTHWORK SUMMARY							
LOCATION	EARTH EXCAVATION	ADDITIONAL EXCAVATION	SHRINKAGE FACTOR	% USED	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT REQUIRED	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	CUBIC YARD	CUBIC YARD			CUBIC YARD	CUBIC YARD	CUBIC YARD
FAP 328 US 45							
STAGE I							
804+55 TO 807+80	30		25.00%	100.00%	23	175	-152
808+97.5 TO 812+70	36		25.00%	100.00%	27	287	-260
STAGE II							
804+55 TO 807+80	57		25.00%	100.00%	43	309	-266
808+97.5 TO 812+70	33		25.00%	100.00%	25	305	-280
CHANNEL EXCAVATION		470	25.00%	100.00%	353		353
	156	470			471	1076	-605
20400800 FURNISHED EXCAVATION =						605	CU.YD.

STAGING SCHEDULE						
LOCATION	TEMPORARY CONCRETE BARRIER	RELOCATE TEMPORARY CONCRETE BARRIER	IMPACT ATTENUATORS TEMPORARY (NON-REDIRECTIVE) TEST LEVEL 3	IMPACT ATTENUATORS RELOCATE (NON-REDIRECTIVE) TEST LEVEL 3	TEMPORARY BRIDGE TRAFFIC SIGNALS	TEMPORARY RUMBLE STRIP
	70400100	70400200	Z0030250	Z0030350	70106500	70106700
FAP 328 US 45						
STAGE I						
LT. STA. 805+96.85 TO LT. STA. 811+80.65	450		2		1	6
STAGE II						
RT. STA. 804+96.85 TO RT. STA. 810+80.65		425		2		
TOTAL	450	425	2	2	1	6

RIGHT OF WAY MARKER SCHEDULE	
LOCATION	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS
	66600105 EACH
FAP 328 US 45	
40' LT. STA. 806+50	1
50' LT. STA. 806+50	1
40' LT. STA. 810+50	1
50' LT. STA. 810+50	1
40' RT. STA. 806+50	1
65' RT. STA. 806+50	1
65' LT. STA. 811+56.76	1
65' RT. STA. 811+85.15	1
TOTAL	8