

**PAVEMENT MARKING SCHEDULE EASTBOUND LANES**

STATION TO STATION				THPL PAVEMENT MARKING				TEMPORARY			SHORT TERM PVT MARKING	NOTES
				4 INCH WHITE	4 INCH YELLOW	6 INCH SKIP-DASH YELLOW	LETTERS & SYMBOLS	4 INCH	6 INCH	LETTERS & SYMBOLS		
				FOOT	FOOT	FOOT	SO FT	FOOT	FOOT	SO FT	FOOT	
<b>Williamson Co. Westbound Lanes</b>												
<b>CL IL 13 WBL - STA. 513+64 TO STA. 539+03</b>												
	513+64.0	TO	539+03.0			635			635		508	
LT	513+64.0	TO	522+98.0	934				934			75	See note 1.
LT	524+55.0	TO	539+03.0	1,448				1,448				
LT	524+55.0	TO	526+56.0	201				201				Rt. Turn Ln. Line
LT	526+56.0	TO	528+81.0								18	See note 1.
LT	528+81.0	TO	539+03.0								82	See note 1.
RT	513+64.0	TO	523+18.0		954			954			76	See note 1.
RT	524+04.0	TO	539+03.0		1,499			1,499			120	See note 1.
LT	526+10.0						15.6			15.6		Rt Turn Arrow @ Nixville Rd.
LT	526+38.0						20.8			20.8		ONLY @ Nixville Rd.
				<b>2,583</b>	<b>2,453.0</b>							
<b>Sub-Totals WBL's Williamson Co.</b>					<b>5,036</b>	<b>635</b>	<b>36.4</b>	<b>5,036</b>	<b>635</b>	<b>36.4</b>	<b>879</b>	
<b>Saline County Westbound Lanes</b>												
<b>CL IL 13 WBL - STA. 539+03 TO STA. 751+50</b>												
	539+03.0	TO	651+98.0			2,824			2,824		2,259	
RT	539+03.0	TO	546+57.0		754			754			60	See note 1.
RT	547+38.0	TO	638+87.0		9,149			9,149			732	See note 1.
RT	639+72.0	TO	651+98.0		1,226			1,226				
RT	646+36.0	TO	651+98.0								45	See note 1.
LT	539+03.0	TO	545+98.0	695				695			56	See note 1.
LT	548+11.0	TO	638+36.0	9,025				9,025				
LT	548+11.0	TO	550+19.0	208				208				Rt. Turn Ln. @ Faith Chapel Rd.
LT	550+19.0	TO	552+51.0								19	See note 1.
LT	552+51.0	TO	638+36.0								687	See note 1.
LT	549+73.0						15.6			15.6		Rt. Turn Arrow @ Faith Chapel Rd.
LT	550+01.0						20.8			20.8		ONLY @ Faith Chapel Rd.
LT	640+40.0	TO	651+98.0	1,158				1,158				
LT	643+55.0	TO	646+56.0								24	See note 1.
LT	646+56.0	TO	651+98.0								43	See note 1.
RT	639+79.0	TO	643+35.0	356				356				Lt. Turn Ln. Line @ Harco Rd.
LT	640+39.0	TO	643+56.0	317				317				Rt. Turn Ln. Line @ Harco Rd.
LT	641+24.0						15.6			15.6		Rt. Turn Arrow @ Harco Rd.
LT	641+52.0						20.8			20.8		ONLY @ Harco Rd.
LT	643+10.0						15.6			15.6		Rt. Turn Arrow @ Harco Rd.
LT	643+38.0						20.8			20.8		ONLY @ Harco Rd.
RT	641+03.0						15.6			15.6		Lt. Turn Arrow @ Harco Rd.
RT	641+31.0						20.8			20.8		ONLY @ Harco Rd.
RT	642+89.0						15.6			15.6		Lt. Turn Arrow @ Harco Rd.
RT	643+17.0						20.8			20.8		ONLY @ Harco Rd.
<b>EXIST. STRUCTURE</b>				<b>OMIT STR. NO. 083-0051 - STA. 651+98 TO STA. 653+36</b>								
	653+36.0	TO	724+21.2			1771			1771		1417	
RT	653+36.0	TO	712+66.0		5930			5930			474	See note 1.
RT	713+53.0	TO	724+21.2		1068			1068				
RT	718+34.0	TO	724+21.2								47	See note 1.
LT	653+36.0	TO	712+38.0	5902				5902			472	See note 1.
LT	714+05.0	TO	724+21.2	1016				1016				
LT	716+09.0	TO	718+39.0								18	See note 1.
LT	718+39.0	TO	724+21.2								47	See note 1.
RT	713+57.0	TO	716+04.0	247				247				Lt. Turn Ln. Line @ Hankins Rd.
LT	714+05.0	TO	716+10.0	205				205				Rt. Turn Ln. Line @ Hankins Rd.
LT	715+64.0						15.6			15.6		Rt. Turn Arrow @ Hankins Rd.
LT	715+92.0						20.8			20.8		ONLY @ Hankins Rd.
RT	715+58.0						15.6			15.6		Lt. Turn Arrow @ Hankins Rd.
RT	715+86.0						20.8			20.8		ONLY @ Hankins Rd.
<b>EO. STA. 724+21.21 (BK) = STA. 725+01.02 (AH)</b>												
	725+01.0	TO	751+50.0			662			662		530	
RT	725+01.0	TO	751+50.0		2649			2649			212	See note 1.
LT	725+01.0	TO	751+50.0	2649				2649			212	See note 1.
				<b>21,778</b>	<b>20,776</b>							
<b>Sub-Totals EBL's Saline Co.</b>					<b>42,554</b>	<b>5,257</b>	<b>254.8</b>	<b>42,554</b>	<b>5,257</b>	<b>254.8</b>	<b>7,354</b>	
<b>TOTALS WESTBOUND LANES</b>					<b>47,590</b>	<b>5,892</b>	<b>291.2</b>	<b>47,590</b>	<b>5,892</b>	<b>291.2</b>	<b>8,233</b>	

Note 1: Quantify under Short-Term Pavement Marking Is for diagonals on shoulder.

\*WILLIAMSON/SALINE COUNTIES

FILE NAME =	USER NAME = mcoardkr	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>PAVEMENT MARKING SCHEDULE</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
at\pvc\work\pavdot\mcoardkr\d0209826\78218-sht-plendgn	DRAWN -	REVISED -	331			09_PAVT_PRES_EVII-1	21	8		
PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -	CONTRACT NO. 78218							
PLOT DATE = 2/3/2011	DATE -	REVISED -	SCALE: _____			SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	ILLINOIS FED. AID PROJECT		