

# SUMMARY OF QUANTITIES

COUNTY:	WILLIAMSON
LOCATION:	URBAN
ROUTE:	FAT 57 (I-57)
FUNDING:	90% FEDERAL 10% STATE
WORK TYPE:	ROADWAY

CODE NUMBER	ITEM DESCRIPTION	CONSTRUCTION TYPE CODE:	
		UNIT	QUANTITY
			0001
X0327230	SURFACE MOUNT LANE SEPARATOR (STATE OWNED)	FOOT	200
20013798	CONSTRUCTION LAYOUT	L SUM	1
20026346	NIGHTTIME WORK ZONE LIGHTING	L SUM	1
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	14
20200100	EARTH EXCAVATION	CU YD	596
20400800	FURNISHED EXCAVATION	CU YD	6836
20800150	TRENCH BACKFILL	CU YD	135
* 25000115	SEEDING, CLASS 1B	ACRE	1.1
* 25000350	SEEDING, CLASS 7	ACRE	1.1
* 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	134
* 25000500	PHOSPHOROUS FERTILIZER NUTRIENT	POUND	93
* 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	93
* 25000700	AGRICULTURAL GROUND LIMESTONE	TON	2
* 25100115	MULCH, METHOD 2	ACRE	1.1
* 25100630	EROSION CONTROL BLANKET	SQ YD	5746
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	103
28000305	TEMPORARY DITCH CHECKS	FOOT	84
28000400	PERIMETER EROSION BARRIER	FOOT	2240
28000500	INLET AND PIPE PROTECTION	EACH	4
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	7294
30201500	LIME	TON	217
31100300	SUB BASE GRANULAR MATERIAL, TYPE A 4"	SQ YD	37
40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	5,171
40600300	AGGREGATE (PRIME COAT)	TON	35
40600895	CONSTRUCTING TEST STRIP	EACH	3
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	4,727
40603345	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	670
42001300	PROTECTIVE COAT	SQ YD	50
44000155	HOT-MIX ASPHALT SURFACE REMOVAL, 1 1/2"	SQ YD	221
44003100	MEDIAN REMOVAL	SQ FT	1445
44004250	PAVED SHOULDER REMOVAL	SQ YD	1844
48100700	AGGREGATE SHOULDERS, TYPE A 8"	SQ YD	346
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	1053
48203100	HOT-MIX ASPHALT SHOULDERS	TON	21

\*SPECIALTY ITEM

FILE NAME =	USER NAME = *USER*	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>				F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*FILEL*		DRAWN -	REVISED -		SCALE: N.T.S.	SHEET NO. 1 OF 2 SHEETS	STA.	TO STA.	331	(IX-1A-1,R-6,N-6,TS-5)	WILLIAMSON	52	5
	PLOT SCALE = *SCALE*	CHECKED -	REVISED -						CONTRACT NO. 78223				
	PLOT DATE = *DATE*	DATE -	REVISED -						ILLINOIS FED. AID PROJECT				