SUMMARY OF QUANTITIES

COUNTY:	WILLIAMSON
LOCATION:	URBAN
ROUTE:	FAI 57 (I-57)
FUNDING:	90% FEDERAL 10% STATE
WORK TYPE:	ROADWAY

CODE NUMBER	ITEM DESCRIPTION	UNIT	QUANTITY	CONSTRUCTION TYPE CODE: 0001
50104400	CONCRETE HEADWALL REMOVAL	EACH	1	1
5421A015	PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY)	FOOT	104	104
5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	58	58
5421A024	PIPE CULVERTS, CLASS A, TYPE 1 24" (TEMPORARY)	FOOT	95	95
54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	3	3
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	2	2
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"	EACH	2	2
60608600	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-6.06	FOOT	125	125
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	281	281
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	4
67100100	MOBILIZATION	L SUM	1	1
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1
70100320	TRAFFIC CONTROL AND PROTECTION, STANDARD 701422	L SUM	1	1
70103810	TRAFFIC CONTROL SURVEILLANCE AND MAINTENANCE	CAL DA	16	16
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2210	2210

*SPECIALTY ITEM

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS / SHEET NO.
		DRAWN -	REVISED -			331	(1X-1)A-1,R-6,N-6,TS-5	WILLIAMSON	52 / 6
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -					CONTRACT NO. 78223	
	PLOT DATE = $DATE$	DATE -	REVISED -		SCALE: N.T.S. / SHEET NO. 2 OF 2 SHEETS / STA. / TO STA.			ILLINOIS FED. AID PROJECT	