EARTHWORK

LOCATION STATION TO STATION	EARTH EXCAVATION	FOR INFORMATION ONLY					FURNISHED EXCAVATION
		AVERAGE SHRINKAGE FACTOR	EARTH EXCAVATION (ADJUSTED)	EMBANKMENT	EARTHWORK BALANCE WASTE (+) SHORTAGE (-)	BORROW SWELL FACTOR	
	CU YD	%	CU YD	CU YD	CU YD	%	CU YD
IL 13							
STA 1802+97 TO STA 1822+50	310	47.1	146	1645	-1499	0.18	1769
TEMPORARY RAMP A							
STA 11+33.78 TO STA 13+94.97	49	41.7	20	2628	-2608	0.18	3077
TEMPORARY RAMP B							
STA 20+26.16 TO STA 21+80.91	50	47.1	24	722	-698	0.18	824
TEMPORARY RAMP C							
STA 7+49.25 TO STA 9+99.81	161	59.2	95	774	-679	0.18	801
TEMPORARY RAMP D							
STA 126+66.22 TO STA 129+13.34	26	41.7	11	320	-309	0.18	365
PROJECT TOTAL	596	-	-	-	-	-	6836

TREE REMOVAL

LOCATION STATION TO STATION	OFFSET FROM E.P.	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	REMARKS
	FEET	UNIT	
TEMP. RAMP A			
STA 11+79	31.5 LT	14	CEDAR
PROJECT TOTALS	-	14	

FILE NAME = $FILEL$	USER NAME = $USER$	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = $SCALE$	CHECKED -	REVISED -
	PLOT DATE = $DATE$	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

EARTHWORK AND TREE REMOVAL SCHEDULES

SCALE: N.T.S. | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
331	(1X-1)A-1,R-6,N-6,TS-5	WILLIAMSON	52	14
		CONTRACT NO. 78223		
		ILLINOIS FED. AID PROJECT		