



RT. 46.1' STA. 1803+99.72 (IL RTE 13)
 REMOVE EXISTING HEADWALL AND
 EXTEND WITH PIPE CULVERTS, CLASS A,
 TYPE 1 15" (TEMPORARY), 59"
 DSFL = 449.26
 CONCRETE HEADWALL REMOVAL, 1 EACH
 PRECAST REINFORCED CONCRETE FLARED END SECTION 15', 1 EACH

PROP. CURVE NWRT13-1
 PI STA. = 1801+39.75
 Δ = 24° 05' 18" (LT)
 D = 0° 57' 50"
 R = 5,944.76'
 T = 1,268.39'
 L = 2,499.31'
 E = 133.81'
 P.C. STA. = 1788+71.36
 P.T. STA. = 1813+70.67

NOTE:
 SEE TYPICAL SECTIONS. SOME TYPE II BARRICADES ARE REQUIRED
 DURING DAY TIME ONLY AT LIMITS OF SHOULDER DROP-OFFS
 OR OPEN TRENCHES.

- TYPE II BARRICADE
- ▨ TEMPORARY RAMP
10 1/2" BINDER AND 1/2" SURFACE
8" SHOULDER
- ▨ TEMPORARY RAMP
VAR. DEPTH BINDER AND
1/2" SURFACE, 1/2" MIN. SHOULDER
- ▨ PAVEMENT REMOVAL AND
PLACEMENT OF 10 1/2" BINDER
AND 1/2" SURFACE
- ▨ PROPOSED WIDENING
10 1/2" BINDER AND 1/2" SURFACE

MARION

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	PLAN VIEW & TRAFFIC CONTROL ILLINOIS ROUTE 13		F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
*FILEL#		DRAWN -	REVISED -		SCALE: 1" = 50'	SHEET NO. 2 OF 5 SHEETS	STA. 1800+00 TO STA. 1815+00	331	(1X-1)A-1,R-6,N-6,TS-5	WILLIAMSON	52	20
PLOT SCALE = #SCALE#		CHECKED -	REVISED -								CONTRACT NO. 78223	
PLOT DATE = #DATE#		DATE -	REVISED -								ILLINOIS FED. AID PROJECT	