

SUMMARY OF QUANTITIES

ITEM NUMBER	ITEM	QUANTITY	UNIT
20200100	EARTH EXCAVATION	800	CU YDS
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	1635	SQ YDS
28000400	PERIMETER EROSION BARRIER	663	FOOT
28000500	INLET AND PIPE PROTECTION	1	EACH
31101000	SUB-BASE GRANULAR MATERIAL, TYPE B	630	TON
X3112800	SUB-BASE GRANULAR MATERIAL (SPECIAL)	615	TON
40300100	BITUMINOUS MATERIALS (PRIME COAT)	680	GALLON
40600100	BITUMINOUS MATERIALS (PRIME COAT)	85	GALLON
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	250	TON
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	150	TON
44000100	PAVEMENT REMOVAL	1002	SQ YDS
48101200	AGGREGATE SHOULDERS, TYPE B	105	TON
542C1069	PIPE CULVERTS, CLASS C, TYPE 2, 24"	66	FOOT
54215559	METAL END SECTIONS 24"	1	EACH
60240395	INLET, TYPE B	1	EACH
67100100	MOBILIZATION	1	L SUM
X7010216	TRAFFIC CONTROL & PROTECTION (SPECIAL)	1	L SUM

NEW ROAD EARTHWORK SCHEDULE						
STATION	AREAS SQUARE FEET		VOLUMES CUBIC YARDS		CUMULATIVE VOLUMES CUBIC YARDS	
	CUT	FILL	CUT	FILL	CUT	FILL
249+25.23	0	0				
249+50	3.84	.79	1.8	0.4	1.8	0.4
250+00	11.72	6.54	14.4	6.8	16.2	7.1
250+20.71	12.75	8.96	9.4	5.9	25.6	13.1
250+50	40.47	9.84	28.9	10.2	54.4	23.3
251+00	113.22	8.81	142.3	17.3	196.7	40.6
251+50	128.68	0	224.0	8.2	420.7	48.7
252+00	105.1	0	216.5	0	637.2	48.7
252+30.58	48.56	0	87	0	724.2	48.7
252+50	13.91	6.38	22.5	2.3	746.7	51
253+00	0	117.62	12.9	114.8	759.5	165.8
253+50	0	197.47	0	291.8	759.5	457.6
254+00	.32	36.76	0.3	216.9	759.8	674.5
254+50	13.55	17.70	12.8	50.4	772.7	724.9
255+00	7.17	2.92	19.2	19.1	791.9	744.0
255+50	0	0	6.6	2.7	798.5	746.7
			0	0	798.5	746.7
TOTALS					799	747