

| RAMP UPGRADE SCHEDULE | | | | | | | | |
|---------------------------------------|-----------------------------|-------------|-------------|----------------|---------------------------|---------------------|--------------------|------------------|
| LOCATION | CORNER LOCATION / DIRECTION | TYPE A RAMP | TYPE B RAMP | GUTTER REMOVAL | CONCRETE GUTTER (SPECIAL) | DETECTABLE WARNINGS | PC CONC SIDEWALK 4 | SIDEWALK REMOVAL |
| | | (EACH) | (EACH) | (LIN FT) | (LIN FT) | (SQ FT) | (SQ FT) | (SQ FT) |
| ADA RAMP UPGRADE | | | | | | | | |
| SUNKIST DRIVE AT CORNSILK COURT | SE/W, SW/E | 2 | | 16 | 16 | 16 | 180 | 144 |
| SUNKIST DRIVE AT ZIMMERMAN DR | SW/N, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| HARVEST COURT / PARKVIEW | SE/W, NE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| HARVEST COURT / PARKVIEW | SW/E, NW/E | 2 | | 16 | 16 | 16 | 180 | 144 |
| HARVEST COURT / PARKVIEW | SW/N, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| FIRST STREET AT PARTRIDGE PASS | SE/N, NE/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| FIRST STREET AT THRUSH COURT | SE/N, NE/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| FIRST STREET / WOOD DUCK CT | SW/N | 1 | | 8 | 8 | 8 | 90 | 72 |
| RAMBLEWOOD / TIMBER EDGE | SW/N, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| RAMBLEWOOD / TIMBER EDGE | SW/E, SE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| RAMBLEWOOD / TIMBER EDGE (SEE SHT 20) | NW/SE, SE/NW | | | 16 | 16 | 16 | 87 | 34 |
| RAMBLEWOOD / MALLARD WAY | SW/E, SE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| RAMBLEWOOD / PHEASANT RUN | SW/E, SE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| RAMBLEWOOD / PHEASANT RUN | SE/N, NE/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| RAMBLEWOOD / PHEASANT RUN | NW/E, NE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| RAMBLEWOOD / PHEASANT RUN | SE/N, NE/S | 2 | 1 | 8 | 8 | 8 | 142 | 104 |
| MEREDITH DR / SARATOGA CHASE | SE/N, NE/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| MEREDITH DR / HARROW DR | NW/E, NE/W | 2 | | 16 | 16 | 16 | 284 | 208 |
| MEREDITH DR / LOST TREE DR | SW/N, NW/S | | 2 | 16 | 16 | 16 | 284 | 208 |
| MEREDITH DR / LOST TREE DR | SE/N, NE/S | | 2 | 16 | 16 | 16 | 180 | 144 |
| MEREDITH DR / LOST TREE DR | NW/E, NE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| MEREDITH DR / FIELDSIDE LN | NW/E, NE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / GREEN MEADOW DR | SW/N, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / GREEN MEADOW DR | SE/N, NE/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / GREEN MEADOW DR | SW/E, SE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / GREEN MEADOW DR | NW/E, NE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / PARKVIEW DR | SE/N, NE/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE / PRAIRIE PLACE | SW/N, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / SUNKIST DR | SW/N, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / SUNKIST DR | SW/E, NW/E | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / POSSUM PASS CT | SE/W, SE/N | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / POSSUM PASS CT | NW/E, NW/S | 2 | | 16 | 16 | 16 | 180 | 144 |
| LOST TREE DR / RAMBLEWOOD | NW/S, NW/E | 2 | | 16 | 16 | 16 | 180 | 144 |
| TURTLE DOVE / GROUSE CT | SW/E, SE/W | 2 | | 16 | 16 | 16 | 180 | 144 |
| TOTALS | | 57 | 5 | 512 | 512 | 512 | 5,927 | 4,658 |

| TREE SCHEDULE | | | | | | | |
|---------------------|---|--------------------------------|----------------------------|---|---|---|-----------------------|
| LOCATION | 20100110 TREE REMOVAL (6 TO 15 UNITS DIA) | 20101100 TREE TRUNK PROTECTION | 20101200 TREE ROOT PRUNING | 20101300 TREE PRUNING (1 TO 10 INCH DIAMETER) | A2000724 TREE, ACER PLATANOIDES COLUMNARE, (COLUMNAR NORWAY MAPLE), 3" CALIPER BALLED AND BURLAPPED | D2003772 EVERGREEN, THUJA OCCIDENTALIS (AMERICAN ARBORVITAE), 6' HEIGHT, BALLED AND BURLAPPED | XX007001 ROOT BARRIER |
| | (UNIT) | (EACH) | (EACH) | (EACH) | (EACH) | (EACH) | (EACH) |
| FIRST STREET | | | | | | | |
| STA 100+13, 1' LT | 8 | | | | | | |
| STA 100+36, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 100+62, 15' LT | | 1 | 1 | 1 | | | 1 |
| STA 100+70, 14' LT | | 1 | 1 | 1 | | | 1 |
| STA 101+69, 1' LT | 4 | | | | | | |
| STA 101+70, 4' LT | 4 | | | | | | |
| STA 102+15, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 102+46, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 102+96, 4' LT | 4 | | | | | | |
| STA 103+84, 7' LT | | 1 | 1 | 1 | | | 1 |
| STA 103+93, 2' LT | 6 | | | | | | |
| STA 104+28, 5' RT | | | | | | 1 | 1 |
| STA 104+38, 5' RT | | | | | | 1 | 1 |
| STA 104+46, 2' RT | 4 | | | | | | |
| STA 104+48, 5' RT | | | | | | 1 | 1 |
| STA 104+57, 1' RT | 4 | | | | | | |
| STA 104+60, 5' RT | | | | | 1 | | 1 |
| STA 104+65, 3' RT | 4 | | | | | | |
| STA 104+70, 5' RT | | | | | | 1 | 1 |
| STA 104+80, 5' RT | | | | | | 1 | 1 |
| STA 104+90, 5' RT | | | | | | 1 | 1 |
| STA 105+02, 5' RT | | | | | 1 | | 1 |
| STA 105+15, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 105+25, 1' LT | 6 | | | | | | |
| STA 105+34, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 105+46, 5' RT | | | | | | 1 | 1 |
| STA 105+56, 5' RT | | | | | | 1 | 1 |
| STA 105+66, 5' RT | | | | | | 1 | 1 |
| STA 105+88, 2' RT | 6 | | | | | | |
| STA 105+99, 1' LT | 6 | | | | | | |
| STA 106+09, 1' LT | 6 | | | | | | |
| STA 106+22, 2' RT | | 1 | 1 | 1 | | | 1 |
| STA 106+30, 4' RT | | 1 | 1 | 1 | | | 1 |
| STA 106+40, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 107+44, 3' RT | | 1 | 1 | 1 | | | 1 |
| STA 107+54, 0' RT | 4 | | | | | | |
| STA 108+29, 0' RT | 4 | | | | | | |
| TOTAL | 70 | 12 | 12 | 12 | 2 | 9 | 23 |

| EARTH EXCAVATION SCHEDULE | | | | |
|---------------------------------------|---------------------------------|---|-------------------|---|
| LOCATION | 20200100 EARTH EXCAVATION [CUT] | EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%) | EMBANKMENT [FILL] | EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) |
| | (CU YD) | (CU YD) | (CU YD) | (CU YD) |
| 1st & SOUTH STREETS | 81.0 | 60.8 | 5.7 | 55.1 |
| TOTALS | 81.0 | 60.8 | 5.7 | 55.1 |
| 20400800 FURNISHED EXCAVATION (CU YD) | | | | 0 |

| SIGN SCHEDULE | |
|---|--------------------------|
| LOCATION | RELOCATE EX SIGNS (EACH) |
| N.W. CORNER OF HARVEST CT. & PARKVIEW DR. | 1.0 |
| S.E. CORNER OF FIRST ST. & PARTRIDGE PASS | 1.0 |
| TOTAL | 2.0 |

| DRAINAGE SCHEDULE | | |
|-------------------------------------|--------------------------------------|--------------------------------|
| LOCATION | PIPE CULVERTS CL A, TY 1, 12" (FOOT) | PRC FL END SECTIONS 12" (FOOT) |
| FIRST ST. & SIDEWALK LT STA. 107+38 | 14.0 | 1 |
| TOTALS | 14.0 | 1 |

| ESTIMATED QUANTITIES SCHEDULE | | |
|-------------------------------|---|--|
| LOCATION | 21400100 GRADING AND SHAPING DITCHES (FOOT) | |
| FIRST & SOUTH STREETS | 50 | |
| TOTAL | 50 | |