



CONCRETE GUTTER (SPECIAL)
 DEPRESS GUTTER 4' @ RAMP
 w/ 2' TRANSITION TO EXISTING,
 8' TOTAL LENGTH EACH.

NOTE:
 PR PCC SIDEWALKS AND RAMPS
 TO BE 4' WIDE AND 4" THICK.
 RAMP SLOPES 8.33% (1:12) TYP.
 COSTS FOR INCIDENTAL EARTHWORK
 AND SEEDING TO BE INCLUDED IN THE
 COST FOR PC CONC SIDEWALK 4 INCH.
 ALL MEASUREMENTS ON CURVES
 ARE CHORD DISTANCES.

BILL OF MATERIALS

| | |
|---------------------------------|------------|
| TOTAL PC CONC SIDEWALK 4 INCH | = 87 SQ FT |
| TOTAL SIDEWALK REMOVAL | = 34 SQ FT |
| TOTAL CONCRETE GUTTER (SPECIAL) | = 16 FT |
| TOTAL GUTTER REMOVAL | = 16 FT |
| DETECTABLE WARNING | = 16 SQ FT |

| | | | |
|--|----------------------------|------------|-----------|
| FILE NAME = | USER NAME = IE Consultants | DESIGNED - | REVISED - |
| G:\507209-01\ced\2010\7009-01.Ent_Detail | BS.SHT | DRAWN - | REVISED - |
| | PLOT SCALE = 5.0000' / 1" | CHECKED - | REVISED - |
| | PLOT DATE = 2/14/2011 | DATE - | REVISED - |

VILLAGE OF SHERMAN

**RAMBLEWOOD / TIMBER EDGE
 SIDEWALK RAMP DETAILS**

| | | | | |
|---|----------------|-----------|--------------|-----------|
| F.A. RTE. | SECTION | COUNTY | TOTAL SHEETS | SHEET NO. |
| | 08-00014-00-SW | SANGAMON | 26 | 26 |
| CONTRACT NO. 93486 | | | | |
| SCALE: | SHEET NO. | OF SHEETS | STA. | TO STA. |
| | | | | |
| FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT | | | | |