

FAU RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982		SANGAMON	63	5
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
10-00447-04-PV		CITY OF SPRINGFIELD		

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION ITEM	UNIT	ROADWAY	
			URBAN TOTAL QUANTITY	ROADWAY CAPITOL AVENUE 10-00447-04-PV NON-ITEP ELIGIBLE ITEMS
				0004
				0031
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	235	235
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	1413	1413
44000600	SIDEWALK REMOVAL	SQ FT	8352	8352
50200100	STRUCTURE EXCAVATION	CU YD	341	341
50300225	CONCRETE STRUCTURES	CU YD	88	88
50800105	REINFORCEMENT BARS	POUND	16460	16460
550B0010	STORM SEWERS, CLASS B, TYPE 1 4"	FOOT	13	13
55100500	STORM SEWER REMOVAL 12"	FOOT	91	91
59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	57	57
* 60107600	PIPE UNDERDRAINS 4"	FOOT	1023	1023
* 60108100	PIPE UNDERDRAINS 4" (SPECIAL)	FOOT	125	125
60255500	MANHOLES TO BE ADJUSTED	EACH	5	5
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5
60500060	REMOVING INLETS	EACH	5	5
* 60603700	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.06 (MODIFIED)	FOOT	1356	1356
60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	704	704
60608250	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.06	FOOT	151	151
60608300	COMBINATION CONCRETE CURB AND GUTTER, TYPE M-2.12	FOOT	297	297
67100100	MOBILIZATION	L SUM	1	1
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	12	12
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1075	1075
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	136	136
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	5808	5090
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	2552	2174

* PAY ITEM REQUIRES A SPECIAL PROVISION

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SUMMARY OF QUANTITIES
 FAU RTE 7982 CAPITOL AVE
 SEC NO. 10-00447-04-PV
 SANGAMON COUNTY, ILLINOIS
 SCALE: VERT. DRAWN BY RSJ
 HORIZ. CHECKED BY MH
 DATE 11/19/10



© Copyright Hanson Professional Services Inc. 2011
 LAYOUT TCD 03/27/07
 DRAWN TCD 03/27/07
 REVIEWED MH / / /
 PLOT DATE = 01/20/2011
 FILE NAME = I:\82\jobs\82526\8\ACADD\Road\Road\MicroStation\Sheet\Section_3-11th - 18th\9-204_SQO.dgn
 PLOT SCALE = 50/000 / / in.
 USER NAME = JohnM0914