

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982		SANGAMON	63	11
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
10-00447-04-PV	CITY OF SPRINGFIELD			

TEMPORARY ACCESS AND FENCING SCHEDULE

LOCATION				AGGREGATE FOR TEMPORARY ACCESS	TEMPORARY SIDEWALK	TEMPORARY CONSTRUCTION FENCE	NOTE
BEGIN STATION	OFFSET	END STATION	OFFSET	TON	SQ FT	FOOT	
CAPITOL AVENUE 11TH STREET - 12TH STREET							
66+25.00	40.00	LT	69+50.00	40.00		350	SCHOOL
68+38.12	35.00	RT	69+50.17	35.00		115	VARIOUS
69+47.67	40.00	RT	69+47.69	75.00		40	VARIOUS
69+60.00	40.00	LT	70+00.00		63		INTERSECTION
69+60.00	40.00	RT	70+00.00		63		INTERSECTION
70+05.00		LT	70+50.00			380	INTERSECTION
70+05.00		RT	70+50.00			300	INTERSECTION
VARIOUS						505	
SUBTOTAL				126	680	1010	
CAPITOL AVENUE 12TH STREET - MARTIN LUTHER KING DRIVE							
VARIOUS				79		960	
SUBTOTAL				79		960	
TOTAL				205	680	1970	

EARTHWORK SCHEDULE

LOCATION		SUB-BASE GRANULAR MATERIAL, TYPE C	SPECIAL EXCAVATION
BEGIN STATION	END STATION	TON	CU YD
CAPITOL AVENUE 11TH STREET - 12TH STREET			
66+43.85	69+13.59	66	885
SUBTOTAL		66	885
CAPITOL AVENUE/12TH STREET INTERSECTION			
69+13.59	70+57.46	950	818
SUBTOTAL		950	818
TOTAL		1016	1703

PAVER PAVEMENT SCHEDULE

LOCATION			CONCRETE PAVER PAVEMENT	CONCRETE PAVER SIDEWALK	DETECTABLE WARNINGS, SPECIAL	PAVE-EDGE PAVER RETAINING SYSTEM
BEGIN STATION	END STATION	OFFSET	SQ YD	SQ YD	SQ FT	FOOT
CAPITOL AVENUE 11TH STREET - 12TH STREET						
66+38.00	70+54.00		1038.0	658.0	96	84.0
TOTAL			1038.0	658.0	96	84

MISCELLANEOUS REMOVAL SCHEDULE

LOCATION			FENCE REMOVAL
BEGIN STATION	END STATION	OFFSET	FOOT
CAPITOL AVENUE 11TH STREET - 12TH STREET			
66+22.69	67+97.75	LT	175
68+10.30	69+45.10	LT	135
69+45.00	69+44.38	LT	3
69+45.10	69+45.00	LT	23
SUBTOTAL			336
TOTAL			336

STREETSCAPE SCHEDULE

LOCATION			MARKER FOOTINGS	METAL BENCH, 6' SECTION	TRASH RECEPTACLES	RECYCLING RECEPTACLES	PRECAST PLANTER EDGE TYPE 2	CUSTOM FENCE STONE PIER FOOTINGS	CUSTOM PLANTER FOOTINGS	DECORATIVE STEEL RAILING	STREET LIGHT FOR INFORMATION ONLY	PEDESTRIAN LIGHT - FOR INFORMATION ONLY
BEGIN STATION	END STATION	OFFSET	*EACH	EACH	EACH	EACH	EACH	*EACH	*EACH	FOOT	**EACH	**EACH
CAPITOL AVENUE 11TH STREET - 12TH STREET												
66+38.00	70+54.00		4	4	2	2	12	13	5	386	4	8
TOTAL			4	4	2	2	12	13	5	386	4	8

* NOT A PAY ITEM
 ** THE ITEMS NOTED SHALL HAVE THE CONCRETE FOUNDATION, 2" DUCT STUB OUTS AND ANCHOR BOLTS INSTALLED BY THE CONTRACTOR, AS DETAILED IN THE PLAN. THE INSTALLATION OF ELECTRICAL WIRING AND LIGHTING UNITS WILL BE COMPLETED BY CWLP.

PAVEMENT MARKING SCHEDULE

LOCATION				SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS	EPOXY PAVEMENT MARKING - LINE 8"	EPOXY PAVEMENT MARKING - LINE 12"	NOTE
BEGIN STATION	OFFSET	END STATION	OFFSET	FOOT	SQ FT	FOOT	SQ FT	FOOT	FOOT	FOOT	SQ FT	FOOT	FOOT	
CAPITOL AVENUE/12TH STREET INTERSECTION														
65+25.27	10.22	RT			13		13				13			YIELD LETTERING
69+16.30	3.00	LT	69+37.36	6.11		21	7					21		YELLOW EDGE LINE
69+16.30	3.00	RT	69+37.36	6.11		22	7					22		YELLOW EDGE LINE
69+35.55	6.16	RT	69+40.24	20.49	7		7				7			YIELD ARROWS
69+38.22	6.00	LT	69+38.32	6.64		13	4					13		WHITE EDGE LINE
69+38.41	7.14	RT	69+49.52	30.19		9	3					9		WHITE DOTTED LINE
69+45.00	5.00	LT			15		15				15			THRU-LEFT
69+50.95	29.68	LT	69+72.13	39.60		8	3					8		WHITE DOTTED LINE
69+57.03	37.42	LT	69+72.74	42.39		7	7				7			YIELD ARROWS
69+68.31	52.12	LT			13		13				13			YIELD LETTERING
69+72.00	32.00	RT			15		15				15			THRU-LEFT
69+72.28	40.47	RT	69+78.20	123.91		84	28					84		YELLOW EDGE LINE
69+72.39	39.64	RT	69+85.15	39.31		13	4					13		WHITE EDGE LINE
69+72.45	40.55	LT	69+77.63	126.57		86	29					86		YELLOW EDGE LINE
69+72.56	39.66	LT	69+82.75	39.69		10	3					10		WHITE EDGE LINE
69+75.42	87.63	LT	69+79.95	92.17		6	2						6	DIAGONAL LINE
69+75.75	87.60	RT	69+80.93	82.41		8	3						8	DIAGONAL LINE
69+76.63	108.85	LT	69+78.69	110.92		3	1						3	DIAGONAL LINE
69+77.02	106.35	RT	69+79.38	104.40		4	1						4	DIAGONAL LINE
69+77.63	126.57	LT	69+82.86	40.59		86	29					86		YELLOW EDGE LINE
69+78.20	123.91	RT	69+85.31	40.13		84	28					84		YELLOW EDGE LINE
69+83.00	32.00	LT			15		15				15			THRU-LEFT
69+84.94	42.38	RT	69+97.07	37.96		7	7				7			YIELD ARROWS
69+85.15	39.31	RT	70+08.03	26.16		9	3					9		WHITE DOTTED LINE
69+87.17	52.34	RT			13		13				13			YIELD LETTERING
70+08.12	26.05	LT	70+17.41	5.34		8	3					8		WHITE DOTTED LINE
70+11.00	5.00	RT			15		15				15			THRU-LEFT
70+14.94	20.50	LT	70+20.47	4.52		7	7				7			YIELD ARROWS
70+17.41	5.34	RT	70+17.43	5.19			3					10		WHITE EDGE LINE
70+18.34	5.31	RT	71+25.60			108	36					108		YELLOW EDGE LINE
70+18.39	5.06	LT	71+25.60			108	36					108		YELLOW EDGE LINE
70+29.28	10.00	LT			13		13				13			YIELD LETTERING
70+62.13	3.00	LT	70+68.18	3.00		9	3					9		DIAGONAL LINE
70+83.18	2.00	LT	70+87.21	2.00		6	2					6		DIAGONAL LINE
71+04.24	1.00	LT	71+06.27	1.00		3	1					3		DIAGONAL LINE
SUBTOTAL					136	718	378				136	679	39	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 SCHEDULE OF QUANTITIES

FAU RTE 7982 CAPITOL AVE
 SEC NO. 10-00447-04-PV
 SANGAMON COUNTY, ILLINOIS

VERT. SCALE: HORIZ. DATE 11/19/10
 DRAWN BY: RSJ
 CHECKED BY: MH



LAYOUT: TCJ 03/22/07
 DRAWN: TCJ 03/22/07
 REVIEWED: MH / /

PLOT DATE: 01/29/2011
 FILE NAME: H:\02_08\02520\11A\CADD\Road\Microstation\Sheet\Section_3-11.dwg - 18th VC - 0025_SC-11ED.dgn
 PLOT SCALE: 50.000' / 1" /
 USER NAME: Jofm2014