CONTRACT NO. 93544

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7982	*	SANGAMON	63	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 10-00447-04-PV CITY OF SPRINGFIELD

LIGHTING SCHEDULE
LOCATION INFORMATION FOR CONTRACTOR
WORK TO BE COMPLETED BY CWLP

LOCATION	REMOVE EXISTING UTILITY POLE	REMOVE EXISTING LIGHT POLE	ORNAMENTAL PEDESTRIAN LIGHT *	ORNAMENTAL STREET LIGHT *	NOTES
STATION OFFSET					
CAPITOL AVENUE 11TH STREET - 12TH STREET					
67+03.29 31.71' LT	1		SEE STREETSCAPE PLANS		
67+76.62 20.11' LT	1				
67+74.59 22.01' RT	1				
67+76.73 41.68' RT	1				
68+32.31 31.83' LT	1				
68+72.59 22.76' RT	1				
SUBTOTAL	**6**				
CAPITOL AVENUE/12TH STREET INTERSECTION					
69+54.63 30.70' LT	1				
69+35.00 26.00' LT				1	
69+35.00 26.00' RT				1	
70+20.00 26.00' LT				1	
70+20.00 26.00' RT				1	
SUBTOTAL	**1**			**4**	
CAPITOL AVENUE 12TH STREET - 13TH STREET					
78+86.00 32.50' RT			1		
78+86.00 32.50' LT			1		
71+72.00 32.50' RT			1		
71+73.77 21.00' RT				1	
72+58.00 32.50' RT			1		
72+65.00 32.50' LT			1		
SUBTOTAL			**5**	**1**	
CAPITOL AVENUE/13TH STREET INTERSECTION					
73+40.00 32.50' RT			1		
73+40.00 21.00' LT				1	
73+42.87 21.26' LT	1				
73+45.13 26.36' RT		1			
74+05.00 21.00' RT				1	
74+14.00 32.50' LT					
SUBTOTAL	**1**	**1**	**1**	**2**	
CAPITOL AVENUE 13TH STREET - 14TH STREET					
74+54.62 21.53' LT	1				
74+85.00 32.50' LT			1		
74+85.00 32.50' RT			1		
75+47.71 20.94' LT		1			
75+70.00 32.50' RT			1		
75+73.00 21.00' LT				1	
75+77.49 21.60' LT	1				
76+57.00 32.50' LT			1		
76+57.00 32.50' RT			1		
SUBTOTAL	**2**	**1**	**5**	**1**	
CAPITOL AVENUE/14TH STREET INTERSECTION					
77+42.00 32.50' LT			1		
77+42.00 21.00' RT				1	
78+04.00 21.00' LT				1	
78+08.00 32.50' RT			1		
78+13.00 32.50' LT			1		
SUBTOTAL			**3**	**2**	
CAPITOL AVENUE 14TH STREET - 15TH STREET					
77+47.56 53.30' LT	1				
77+47.83 26.55' RT	1				
77+95.91 26.60' LT	1				
79+06.71 32.50' RT			1		
79+32.91 21.90' LT	1				
79+74.00 21.00' LT				1	
79+87.00 32.50' LT			1		
80+67.00 32.50' LT			1		
80+67.00 32.50' RT			1		
80+68.60 20.33' LT	1				
81+47.30 31.08' RT	1				
82+20.71 21.92' LT	1				
SUBTOTAL	**7**		**4**	**1**	
CAPITOL AVENUE/15TH STREET INTERSECTION					
81+43.00 32.50' RT			1		
81+43.00 21.00' LT				1	
82+07.00 21.00' RT				1	
82+15.00 32.50' LT			1		
SUBTOTAL			**2**	**2**	
CAPITOL AVENUE 15TH STREET - 18TH STREET					
82+73.74 20.97' LT	1				
82+88.00 32.50' LT			1		
82+88.00 32.50' RT			1		
83+76.00 21.00' LT				1	
83+76.00 32.50' RT			1		
84+66.00 32.50' LT			1		
84+66.00 32.50' RT			1		
85+36.00 32.50' LT			1		
85+37.81 21.81' LT		1			
85+44.00 21.00' RT				1	

LIGHTING SCHEDULE
LOCATION INFORMATION FOR CONTRACTOR
WORK TO BE COMPLETED BY CWLP

LOCATION	REMOVE EXISTING UTILITY POLE	REMOVE EXISTING LIGHT POLE	ORNAMENTAL PEDESTRIAN LIGHT *	ORNAMENTAL STREET LIGHT *	NOTES
STATION OFFSET					
85+50.00 24.98' RT		1			
86+09.00 21.00' RT				1	
86+15.00 32.50' LT			1		
86+41.43 21.84' LT	1				
86+77.00 21.00' LT				1	
86+89.00 32.50' RT			1		
86+97.00 32.50' LT			1		
87+44.45 20.67' LT		1			
87+80.00 32.50' RT			1		
87+97.20 200.74' LT	1				
88+52.00 32.50' LT			1		
88+60.00 32.50' RT			1		
89+38.00 32.50' LT			1		
89+45.00 21.00' RT				1	
89+50.74 23.53' RT		1			
89+62.17 21.26' LT	1				
90+10.00 21.00' RT				1	
90+26.00 32.50' LT			1		
90+91.00 32.50' LT			1		
90+96.00 32.50' LT			1		
90+96.77 20.91' LT	1				
91+78.00 21.00' LT				1	
91+78.00 32.50' RT			1		
92+49.00 21.20' LT	1				
92+55.74 22.34' RT		1			
92+56.00 32.50' LT			1		
92+65.00 32.50' RT			1		
SUBTOTAL	**6**	**5**	**19**	**7**	
CAPITOL AVENUE/18TH STREET INTERSECTION					
93+39.00 32.50' LT			1		
93+39.00 21.00' RT				1	
94+11.76 23.37' LT	1				
94+20.00 21.00' LT				1	
SUBTOTAL	**1**		**1**	**2**	
TOTAL	**24**	**7**	**40**	**22**	

* THE ITEMS NOTED SHALL HAVE THE CONCRETE FOUNDATION, 2" DUCT STUB OUTS AND ANCHOR BOLTS INSTALLED BY THE CONTRACTOR, AS DETAILED IN THE PLAN. THE INSTALLATION OF ELECTRICAL WIRING AND LIGHTING UNITS WILL BE COMPLETED BY CWLP.

FIRE HYDRANT SCHEDULE
LOCATION INFORMATION FOR CONTRACTOR
WORK TO BE COMPLETED BY CWLP

LOCATION	FIRE HYDRANTS TO BE REMOVED	FIRE HYDRANTS
STATION OFFSET		
CAPITOL AVENUE/12TH STREET INTERSECTION		
70+13.84 30.51' RT		1
70+13.57 26.80' RT	1	
SUBTOTAL	**1**	**1**
TOTAL	**1**	**1**

UTILITY ADJUSTMENT SCHEDULE

LOCATION	EXISTING ELEVATION	PROPOSED ELEVATION	ELEVATION DIFFERENCE	MANHOLES TO BE ADJUSTED	FRAMES AND LIDS TO BE ADJUSTED	NOTES
STATION OFFSET				EACH	EACH	
2ND ST. INTERSECTION						
MIDBLOCK OF 11TH ST. AND 12TH ST.						
66+70.21 13.90' RT	598.19	597.80	-0.39		1	WATER VALVE
66+71.24 6.07' RT	598.19	597.95	-0.24		1	WATER VALVE
66+74.81 8.37' RT	598.19	597.91	-0.28		1	WATER VALVE
67+31.79 21.00' RT	598.29	598.18	-0.11	1		SEWER
67+93.23 0.11' LT	598.55	598.30	-0.25	1		SEWER
68+83.81 0.06' RT	598.42	598.24	-0.18	1		SEWER
OTAL				**3**	**3**	
12TH ST. INTERSECTION						
69+80.40 0.04' RT	598.42	600.04	1.62	1		SEWER
70+00.75 1.37' RT	598.42	598.99	0.57	1		SEWER
70+13.25 12.36' RT	598.12	598.44	0.32		1	WATER VALVE
70+52.47 26.80' RT	598.02	598.02			1	WATER VALVE
SUBTOTAL				**2**	**2**	
TOTAL				**5**	**5**	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SCHEDULE OF QUANTITIES

FAU RTE 7982 CAPITOL AVE
SEC NO. 10-00447-04-PV
SANGAMON COUNTY, ILLINOIS

SCALE: VERT.
HORIZ.
DATE 11/19/10

DRAWN BY RSJ
CHECKED BY MH

© Copyright Hanson Professional Services Inc. 2011

HANSON

LAYOUT	TCJ	03/27/07
DRAWN	TCJ	03/27/07
REVIEWED	MH	/ /

PLOT DATE = 01\20\2011
FILE NAME = I:\PZ_Jobs\82594A\CADD\Road\Microstation\Sheets\Section_311h - 18th\C-005-SCHED.dgn
PLOT SCALE = 1.5000 ' / in.
USER NAME = johnd80944