

WATER MAIN 4"

LOCATION		FOOT
STA. 13+95.00	TO 13+95.00 RT.	11
TOTAL		11

WATER MAIN 6"

LOCATION		FOOT
STA. 20+59.00	TO 20+59.00 RT.	9
TOTAL		9

WATER MAIN 10"

LOCATION		FOOT
STA. 11+26.00	TO 11+26.00 RT.	21
STA. 11+26.00	TO 16+00.00 RT.	481
STA. 16+00.00	TO 22+00.00 RT.	600
STA. 22+00.00	TO 24+18.00 RT.	235
TOTAL		1,337

WATER VALVES 4"

LOCATION	EACH
STA. 13+95.00 27' RT.	1
TOTAL	1

WATER VALVES 6"

LOCATION	EACH
STA. 20+59.00 27' RT.	1
TOTAL	1

WATER VALVES 10"

LOCATION	EACH
STA. 11+29.00 40' RT.	1
STA. 18+05.00 27' RT.	1
STA. 24+00.00 27' RT.	2
TOTAL	4

TAPPING VALVES AND SLEEVES 6"

LOCATION	EACH
STA. 11+23.00 38' RT.	1
TOTAL	1

WATER SERVICE LINE 1"

LOCATION		FOOT
STA. 16+57.00	TO 15+67.00 RT.	12
STA. 22+86.00	TO 22+85.00 RT.	9
TOTAL		21

FIRE HYDRANT WITH AUXILIARY VALVE AND VALVE BOX

LOCATION	EACH
STA. 14+50.00 27' RT.	1
STA. 18+10.00 27' RT.	1
STA. 21+00.00 27' RT.	1
STA. 23+87.00 27' RT.	1
TOTAL	4

CUT AND CAP EXISTING WATER MAIN

LOCATION	EACH
STA. 11+21.00 35' RT.	1
TOTAL	1

CONNECTION TO EXISTING WATER MAIN

LOCATION		EACH
STA. 11+24.00	TO 19' RT.	1
STA. 20+59.00	TO 27' RT.	1
STA. 24+00.00	TO 18' RT.	1
TOTAL		3

WATER SERVICE CONNECTION 1"

LOCATION		EACH
STA. 16+57.00	TO 27' RT.	1
STA. 22+86.00	TO 31' RT.	1
TOTAL		2

WATER SERVICE CONNECTION 2.5"

LOCATION		EACH
STA. 13+95.00	TO 27' RT.	1
TOTAL		1

WATER MAIN CASING PIPE

LOCATION		FOOT
STA. 11+44.00	TO 11+66.00 RT.	22
STA. 11+90.00	TO 12+12.00 RT.	22
STA. 12+75.00	TO 12+97.00 RT.	22
STA. 13+39.00	TO 13+61.00 RT.	22
STA. 15+22.00	TO 16+09.00 RT.	87
STA. 15+58.00	TO 17+03.00 RT.	45
STA. 19+08.00	TO 19+30.00 RT.	22
STA. 19+94.00	TO 20+16.00 RT.	22
STA. 21+39.00	TO 21+61.00 RT.	22
STA. 22+39.00	TO 22+61.00 RT.	22
STA. 22+64.00	TO 22+82.00 RT.	18
TOTAL		326

TRENCH BACKFILL, WATERMAIN, SPECIAL

LOCATION		FOOT
STA. 11+29.00	TO 11+29.00 RT.	15
STA. 15+14.00	TO 16+00.00 RT.	86
STA. 16+00.00	TO 18+41.00 RT.	241
TOTAL		342

MANHOLES, SANITARY, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID

LOCATION		EACH
STA. 19+19.00	TO 35' RT.	1
TOTAL		1

SANITARY SEWER 12"

LOCATION		FOOT	TBF	CU YD
STA. 19+19.00	TO 19+19.00 LT.	80	99	
STA. 19+19.00	TO 19+19.00 RT.	2	0	
TOTAL		82	99	

IL 45 TO EAST OF BOX
 pr.ctb of Effingham\2009\090198-00-RickelmanAve\Draw

FILE NAME = 0090198_Schd-Quant-west.dgn	USER NAME = #USER#	DESIGNED - PSA	REVISED -	CITY OF EFFINGHAM	RICKELMAN AVE (FAU 8376) SECTION 07-00112-00-PV SCHEDULE OF QUANTITIES	F.A.U. RTE. 8376	SECTION 07-00112-00-PV	COUNTY EFFINGHAM	TOTAL SHEETS 53	SHEET NO. 8	
PLOT SCALE = #SCALE#	CHECKED - PJM	REVISED -	SCALE: N.T.S.			SHEET NO. OF SHEETS	STA. 13+80.0 TO STA. 24+60.0	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT		CONTRACT NO. 95635	
PLOT DATE = 10/19/2010	DATE - 10/19/10	REVISED -									
FARNSWORTH GROUP, INC.		CONSULTING ENGINEERS - 104 NORTH SECOND STREET, SUITE A, EFFINGHAM, IL 62401 (217)342-5668 / (217)342-5853 FAX									