


NOTES:  
 1. ALL EXISTING PAVEMENT MARKINGS THAT CONFLICT WITH PROPOSED MARKINGS SHALL BE REMOVED.  
 2. PAVEMENT MARKING LINES SHALL NOT BE LAID DIRECTLY OVER A LONGITUDINAL OR TRANSVERSE CRACK OR JOINT. THE EDGES OF THE PAVEMENT MARKING LINES SHALL BE OFFSET A MINIMUM OF 2" FROM A LONGITUDINAL OR TRANSVERSE CRACK OR JOINT.



**LEGEND**

- ① EPOXY PAVEMENT MARKING LINE - 4", SOLID WHITE
- ② EPOXY PAVEMENT MARKING LINE - 4", SOLID YELLOW WITH DASHES, 10' LONG W/ 30' GAP (SEE DETAIL 3)
- ③ EPOXY PAVEMENT MARKING LINE - 4", SOLID DOUBLE YELLOW (SEE DETAIL 1)
- ④ EPOXY PAVEMENT MARKING LINE - 4", YELLOW DASHES, 10' LONG W/ 30' GAP
- ⑤ EPOXY PAVEMENT MARKING LINE - 12", SOLID WHITE 45 DEGREE DIAGONAL LINES @ 20' CTS. (SEE DETAIL 2)
- ⑥ EPOXY PAVEMENT MARKING LINE - 12", SOLID YELLOW 45 DEGREE DIAGONAL LINES @ 20' CTS. (SEE DETAIL 2)
- ⑦ EPOXY PAVEMENT MARKING - LETTERS & SYMBOLS (LARGE SIZE)

IL 45 TO EAST OF BOX

FILE NAME - 0000118_PVMTTHAR-west.dgn	USER NAME - #USER#	DESIGNED - PSA	REVISED -	<b>CITY OF EFFINGHAM</b>	<b>RICKELMAN AVE (FAU 8376) SECTION 07-00112-00-PV PAVEMENT MARKING AND SIGNAGE PLAN</b>	F.A.U. RTE. 8376	SECTION 07-00112-00-PV	COUNTY EFFINGHAM	TOTAL SHEETS 53	SHEET NO. 26	
PLOT SCALE = \$SCALE#	PLOT DATE = 10/19/2010	DRAWN - JTC	REVISED -			SCALE: 1"=20'	SHEET NO. OF SHEETS	STA. 13+00.0	TO STA. 22+00.0	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT	CONTRACT NO. 95635
CHECKED - PJM	DATE 10/19/10	REVISOR -	REVISOR -								
		FARNSWORTH GROUP, INC.	CONSULTING ENGINEERS - 104 NORTH SECOND STREET, SUITE A, EFFINGHAM, IL 62401 (217)342-5668 / (217)342-5853 FAX								