

CLEARING AND GRUBBING NOTES

THE AREA DESIGNATED FOR CLEARING AND GRUBBING IS SHOWN ON THIS SHEET. ALL OF THIS AREA IS LOCATED ON EXISTING AIRPORT PROPERTY.

ALL CLEARING AND GRUBBING WILL BE MARKED BY THE RESIDENT ENGINEER.

ALL AREAS DESIGNATED FOR CLEARING AND GRUBBING ARE SHOWN ON THIS SHEET AS .

TWO WEEKS BEFORE BEGINNING THE CLEARING AND GRUBBING OPERATIONS **THE CONTRACTOR WILL** NOTIFY ADJACENT LAND OWNERS AS TO WHAT HIS CONSTRUCTION METHODS WILL BE.

IF PERMITTED BY THE PERTINENT GOVERNING AUTHORITIES, THE CONTRACTOR MAY BURN AND BURY THE CLEARED TREES ON AIRPORT PROPERTY. IF BURNING AND BURIAL IS NOT PERMITTED, THE CONTRACTOR MUST DISPOSE OF THE TREES OFF THE AIRPORT PROPERTY. THE BURNING AND BURIAL LOCATION OF THE TREES WILL BE APPROVED BY THE RESIDENT ENGINEER.

THERE WILL BE AT LEAST TWO FEET OF EARTH PLACED OVER THE BURIED MATERIAL. ALL BURIAL AREAS WILL BE GRADED AND SEEDDED. ALL BURIAL/BURN AREAS WILL BE LOCATED A MINIMUM OF 20 FEET FROM ANY EXISTING OR PROPOSED DITCH.

PRIOR TO ANY SEEDING OPERATIONS, THE AREA WILL BE DISKED WITH A HEAVY DUTY DISK OR RAKED TO REMOVE ROOTS OR DEBRIS FROM THE CLEARING AND GRUBBING OPERATIONS.

ALL AREAS BEING CLEARED AND GRUBBED WILL BE LIGHTLY COMPACTED, SMOOTH GRADED TO DRAIN AND SEEDDED IN ACCORDANCE WITH ITEM 901 "SEEDING" AND MULCHED IN ACCORDANCE WITH ITEM 908 "MULCHING".

CLEARING, GRUBBING AND DISPOSAL OF THE DESIGNATED AREA WILL BE PAID FOR UNDER ITEM: AR151450 "CLEARING AND GRUBBING" _____ PER ACRE.


ADDITIONAL EROSION CONTROL BLANKET NOTES

AN EROSION CONTROL MATERIAL (KNITTED STRAW MAT) 8' IN WIDTH WILL BE INSTALLED ALONG EITHER SIDE OF THE PROPOSED DITCHES AT THE DISCRETION OF THE RESIDENT ENGINEER AS NEEDED. THE CONTRACTOR WILL COORDINATE WITH THE RESIDENT ENGINEER THE AREA AND QUANTITY TO BE COVERED PRIOR TO INSTALLATION. THE QUANTITY, APPROXIMATELY 4,978 S.Y. WAS BASED ON DITCHES EXCEEDING 3 FEET IN DEPTH. AN ADDITIONAL 3,555 S.Y. WAS ESTIMATED TO ASSIST IN EROSION AREAS THAT MAY OCCUR WITHIN THE CLEARING AND GRUBBING LIMITS.

THIS ITEM WILL BE PAID FOR UNDER:
AR156531 "EROSION CONTROL BLANKET" _____ PER S.Y.

LEGEND

- EXISTING IMPROVEMENTS
- PROPOSED IMPROVEMENTS
- PROPOSED CLEARING AND GRUBBING
- EXISTING PROPERTY LINE



MAR 11, 2011 10:39 AM RINKED0461 C:\PWISE_WORK\DO_NOT_DELETE\DM18063\101SIT.DWG

REVISION	DATE

Hanson Proj. No. 10A00553
 Filename R-101SIT.DWG
 Scale 1" = 100'
 Date 03/10/11

LAYOUT BAK 01/11/11
 DRAWN BAK 01/11/11
 REVIEWED xx xx/xx/xx

EDGAR COUNTY AIRPORT
 PARIS, ILLINOIS

IL PROJ.: PRG-4018 A.I.P. PROJ.: 3-17-0077-B13

HANSON
 Professional Services Inc. 2011
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 www.hanson-inc.com
 Offices Nationwide

CONSTRUCT CROSSWIND
 RUNWAY 18-36

PROPOSED
 CLEARING PLAN