



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 11, 2022

SUBJECT FAP Route 370 (Western Ave)  
Project HUBG(930)  
Section 2017-060TS  
Cook County  
Contract 62G03  
Item No. 1, April 29, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page ii of the Table of Contents to the Special Provisions.
3. Added page 93 to the Special Provisions.
4. Revised sheets 3 & 7 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

MTS

VIDEO VEHICLE DETECTION SYSTEM.....	52
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, DETECTOR UNIT.....	53
RELOCATE EXISTING EMERGENCY VEHICLE PRIORITY SYSTEM, PHASING UNIT .....	54
TEMPORARY TRAFFIC SIGNAL INSTALLATION .....	54
TEMPORARY TRAFFIC SIGNAL TIMING .....	61
REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT.....	62
ACCESSIBLE PEDESTRIAN SIGNALS (APS) (BDE) .....	63
BLENDED FINELY DIVIDED MINERALS (BDE).....	64
COMPENSABLE DELAY COSTS (BDE).....	65
CONSTRUCTION AIR QUALITY – DIESEL RETROFIT (BDE).....	68
DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) .....	71
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE).....	80
STEEL COST ADJUSTMENT (BDE).....	81
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) .....	84
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) .....	84
TRAINING SPECIAL PROVISIONS (BDE) .....	85
IDOT TRAINING PROGRAM GRADUATE ON-THE-JOB TRAINING SPECIAL PROVISION.....	87
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) .....	90
WEEKLY DBE TRUCKING REPORTS (BDE).....	90
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) .....	90
WORKING DAYS (BDE) .....	92
ADJUSTMENTS AND RECONSTRUCTIONS (D1) .....	93

Revised 4/11/2022

## **ADJUSTMENTS AND RECONSTRUCTIONS (D1)**

Effective: March 15, 2011

Revise the first paragraph of Article 602.04 to read:

**“602.04 Concrete.** Cast-in-place concrete for structures shall be constructed of Class SI concrete according to the applicable portions of Section 503. Cast-in-place concrete for pavement patching around adjustments and reconstructions shall be constructed of Class PP-1 concrete, unless otherwise noted in the plans, according to the applicable portions of Section 1020.”

Revise the third, fourth and fifth sentences of the second paragraph of Article 602.11(c) to read:

“Castings shall be set to the finished pavement elevation so that no subsequent adjustment will be necessary, and the space around the casting shall be filled with Class PP-1 concrete, unless otherwise noted in the plans, to the elevation of the surface of the base course or binder course. HMA surface or binder course material shall not be allowed. The pavement may be opened to traffic according to Article 701.17(e)(3)b.”

Revise Article 603.05 to read:

**“603.05 Replacement of Existing Flexible Pavement.** After the castings have been adjusted, the surrounding space shall be filled with Class PP-1 concrete, unless otherwise noted in the plans, to the elevation of the surface of the base course or binder course. HMA surface or binder course material shall not be allowed. The pavement may be opened to traffic according to Article 701.17(e)(3)b.”

Revise Article 603.06 to read:

**“603.06 Replacement of Existing Rigid Pavement.** After the castings have been adjusted, the pavement and HMA that was removed, shall be replaced with Class PP-1 concrete, unless otherwise noted in the plans, not less than 9 in. (225 mm) thick. The pavement may be opened to traffic according to Article 701.17(e)(3)b.

The surface of the Class PP concrete shall be constructed flush with the adjacent surface.”

Revise the first sentence of Article 603.07 to read:

**“603.07 Protection Under Traffic.** After the casting has been adjusted and the Class PP concrete has been placed, the work shall be protected by a barricade and two lights according to Article 701.17(e)(3)b.”

Added 4/11/2022