

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE	
				URBAN	
				FED 80%	STATE 20%
				ROADWAY	0005 RURAL
20400800	FURNISHED EXCAVATION	CU YD	1.2	1.2	
21400100	GRADING AND SHAPING DITCHES	FOOT	499	499	
25000210	SEEDING, CLASS 2A	ACRE	0.1	0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	8	8	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	8	8	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	8	8	
25100630	EROSION CONTROL BLANKET	SQ YD	333	333	
28100107	STONE RIPRAP, CLASS A4	SQ YD	42	42	
28200200	FILTER FABRIC	SQ YD	42	42	
35101600	AGGREGATE BASE COURSE, TY B 4"	SQ YD	218	218	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	18	18	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGWAYS	TON	18	18	
40600901	HOT-MIX ASPHALT BINDER COURSE (HAND METHOD), N70	TON	30	30	
40600990	TEMPORARY RAMP	SQ YD	660	660	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	7662	7662	



MODEL: Default  
 FILE: \\nas01c-pw-bentley.com\PWDOT\Documents\DOT\_Offices\DH\dtr\_3\Project\366E51\CAD\data\CADsheets\366E51.rvt-500.dgn

USER NAME = yousifm	DESIGNED - _____	REVISED - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>			F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
DRAWN - _____	REVISIONS - _____	REVISIONS - _____		392	(F)RS-5	GRUNDY	36	3			
PLOT SCALE = 100.0000' / in.	CHECKED - _____	REVISIONS - _____		SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____			CONTRACT NO. 66E51				
PLOT DATE = 1/31/2022	DATE - _____	REVISIONS - _____		ILLINOIS FED. AID PROJECT							

SIDEWALK SCHEDULE FOR NEW RAMP INSTALLATION													
LOCATION SIDE STREET	QUAD	SIDEWALK REMOVAL	PCC SIDEWALK 4"	AGG BASE CSE TY B, 4"	CCC&G REMOVAL	CC&G	FRAMES & LIDS TO BE ADJ	WATER VALVE TO BE ADJ	SODDING *	NITROGEN FERTILIZER NUTRIENT *	PHOSPHORUS FERTILIZER NUTRIENT *	POTASSIUM FERTILIZER NUTRIENT *	DETECTABLE WARNINGS
		SQ FT	SQ FT	SQ YD	FOOT	FOOT	EACH	EACH	SQ YD	POUNDS	POUNDS	POUNDS	SQ FT
CITY													
S KEATING BLVD	SW	49.6	49.6	5.5	8.2	8.2							10
S KEATING BLVD	SE	90.3	90.3	10.0									30
WATERS EDGE RD	NW	131.2	131.2	14.6									44
WATERS EDGE RD	NE	85.2	85.2	9.5									25
WATERS EDGE RD	SW	46.4	46.4	5.2									22
RIDGE RD	NW	73.7	73.7	8.2									38
RIDGE RD	NE	57.2	57.2	6.4									44
RIDGE RD	SW	275.5	275.5	30.6	30	30							44
RIDGE RD	SE	252.8	235.7	26.2	37.4	37.4			18.9	0.35	0.35	0.35	50
PHEASANT LN	SW	101.8	101.8	11.3	16.4	16.4							26
PHEASANT LN	SE	98.9	97.8	10.9	18	18			2.6	0.04	0.04	0.04	24
YELLOW PINE DR	NW	315.7	233.8	26.0	27.9	27.9	1	1	80.2	1.49	1.49	1.49	36
YELLOW PINE DR	NE	103.6	103.6	11.5	9.2	9.2							43
YELLOW PINE DR	SW	178.6	139.8	15.5	26.8	26.8							34.8
YELLOW PINE DR	SE	253.3	241.2	26.8					19.5	0.36	0.36	0.36	53.4
<b>SUBTOTAL</b>		<b>2114</b>	<b>1963</b>	<b>218</b>	<b>174</b>	<b>174</b>	<b>1</b>	<b>1</b>	<b>121</b>	<b>2</b>	<b>2</b>	<b>2</b>	<b>480</b>

\*THESE ITEMS SHALL BE INCLUDED IN THE COST OF THE SIDEWALK PAY ITEMS, AS OUTLINED IN THE SPECIAL PROVISIONS UNDER "PREPARATION AND RESTORATION OF SIDEWALK WORK AREAS"

PAVEMENT MARKING SCHEDULE											
LOCATION			LENGTH	PAINT (2 APPLICATION)			SHORT- TERM PAVEMENT MARK (3 APPS)	SHORT- TERM PAVEMENT MARK REM (1 APP)	RAISED REFLECTIVE PVMT MARK  AMBER EACH	RAISED REFLECTIVE PVMT MARK  CRYSTAL EACH	RAISED REFLECTIVE PVMT MARK  REMOVAL EACH
				4" EOP  WHITE FOOT	4" NO PASS  YELLOW FOOT	6" SKIPS  YELLOW FOOT					
STA	TO	STA									
374+51	TO	434+75	6024.0	12048	4378	3020	1807	201	70	70	
434+75	TO	506+26	7151.0				2145	238	315	100	415
SUB TOTAL				24096	4378	3020	3953	439	385	100	485
PROJECT TOTAL				28474			3953	439	485		485

MODEL: Default  
 FILE: \\nas01c-paw.bentley.com\FWIDOT\Documents\DOT\_Offices\Bartlett\_3\Projects\0366E51\0366E51\CAD\data\0366E51\paw\schedule.dgn

USER NAME = pletschr	DESIGNED - _____	REVISED - _____	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SCHEDULES</b>				F.A.U RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - _____	REVISED - _____		392	(F)RS-5	GRUNDY	36	14				
PLOT SCALE = 100.0000 ' / in.	CHECKED - _____	REVISED - _____		SCALE: _____ SHEET ____ OF ____ SHEETS STA. _____ TO STA. _____				CONTRACT NO. 66E51				
PLOT DATE = 4/4/2022	DATE - _____	REVISED - _____						ILLINOIS FED. AID PROJECT				