



# Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 13, 2022

SUBJECT: FAP Route 567 (IL 38)  
Project NHPP-AK12(674)  
Section (34)RS-7&(7)RS-4,SW  
DeKalb County  
Contract No. 66L50  
Item No. 35, April 29, 2022 Letting  
Addendum A

## NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised the Schedule of Prices.
2. Revised page 7 of the Special Provisions.
3. Revised sheets 4 and 25 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.  
Bureau Chief, Design and Environment

check the correctness of the Contractor's stakes. Any apparent errors will be immediately called to the Contractor's attention and the Contractor will be required to make the necessary correction before the stakes are used for construction purposes. The Contractor shall provide the Engineer a copy of any field notes and layout diagrams produced during the course of the project.

Responsibility of the Contractor. The Contractor shall establish from the given survey points and contract plan information, all the control points or reference points necessary to layout the ADA Ramp elements. The Contractor shall furnish and place the layout stakes. The Contractor shall notify the Engineer when the stakes are complete and available for review and approval by the Engineer at least 3 working days in advance of the actual construction. Field notes shall be kept in standard survey field notebooks and those books shall become the property of the Department at the completion of the project. All notes shall be neat, orderly, and in accepted form.

Measurement and Payment. This work will be paid for at the contract lump sum price for CONSTRUCTION LAYOUT (SPECIAL).

## **PREPARATION OF SIDEWALK WORK AREAS**

(Revised April 4, 2022)

At any location where the existing sidewalk elevations require modification to meet ADA compliance, the work shall include leveling and shaping of the existing ground/subbase to provide the required ADA compliant slopes as shown in the plan details, including any required furnished excavation, earth excavation under the proposed sidewalk necessary to complete the work and restore any disturbed areas.

This work will not be paid for separately, but shall be included in the cost of the applicable sidewalk pay items:

- PORTLAND CEMENT CONCRETE SIDEWALK, 5"
- PORTLAND CEMENT CONCRETE SIDEWALK, 5" (SPECIAL)
- BRICK PAVER REMOVAL AND REINSTALLATION (SPECIAL)
- CONCRETE ISLAND, SPECIAL
- CONCRETE MEDIAN SURFACE, 4"

Earth Excavation required for the removal of non-special waste disposal will be measured and paid separately.

The 4-Inch Aggregate Base Course, Type B (CA 6 material) required for the sidewalks will be measured and paid separately.

## **PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL**

In addition to the requirements of Section 424 of the Standard Specifications the following shall apply:

Description. This work includes the additional effort required to match the existing concrete grooving for the proposed concrete sidewalks located at the north quadrants of the IL 38 and Castle Drive intersection.

Basis of Payment. All proposed sidewalk work at the north quadrants of IL 38 and Castle Drive intersection will be paid for at the contract unit price per square foot as PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL. Revised April 13, 2022