

SUMMARY OF QUANTITIES						CONSTRUCTION CODE	CONSTRUCTION CODE
						80% FEDERAL / 20% VILLAGE OF BARRINGTON	100% VILLAGE OF BARRINGTON
SP	*	CODE NO.	ITEM	UNIT	TOTAL QUANTITY	0028	0028
		550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	242	242	
		550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	144	144	
		550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	338	338	
		55100200	STORM SEWER REMOVAL 6"	FOOT	34	34	
		55100300	STORM SEWER REMOVAL 8"	FOOT	66	66	
		55100500	STORM SEWER REMOVAL 12"	FOOT	418	418	
		56400300	FIRE HYDRANTS TO BE ADJUSTED	EACH	1	1	
		60207005	CATCH BASINS, TYPE C, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
		60218300	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, OPEN LID	EACH	2	2	
		60218400	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
		60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1	1	
		60236200	INLETS, TYPE A, TYPE 8 GRATE	EACH	4	4	
	*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	45	45	△
		60266600	VALVE BOXES TO BE ADJUSTED	EACH	1	1	
	*	66900530	SOIL DISPOSAL ANALYSIS	EACH	2	2	△
SP		60603900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 (ABUTTING EXISTING PAVEMENT)	FOOT	204	204	
	*	66901001	REGULATED SUBSTANCES PR-CONSTRUCTION PLAN	L SUM	1	1	△
SP		60605100	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 (ABUTTING EXISTING PAVEMENT)	FOOT	567	567	
	*	66901003	REGULATED SUBSTANCES FINAL CONSTRUCTION REPORT	L SUM	1	1	△
		67100100	MOBILIZATION	L SUM	1	1	
	*	66901006	REGULATED SUBSTANCES MONITORING	CAL DAY	2	2	△

SP - SPECIAL PROVISION

* SPECIALTY ITEM