



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 20, 2022

SUBJECT: Route FAU 7094 (Maplewood Drive)
Section 20-00115-00-BT
Champaign County
Contract No. 91614
Item 117
April 29, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page 3 of the Special Provisions.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read 'Jack A. Elston'.

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

This work will be paid for at the contract unit price per square foot for SIDEWALK REMOVAL, which price shall include all labor and equipment necessary to complete the work as shown in the plans and as specified by the Engineer.

PORTLAND CEMENT CONCRETE SIDEWALK: This work shall consist of the ~~excavation for and~~ installation of Portland cement concrete sidewalk as shown in the plans and as directed by the Engineer.

This work shall be performed in accordance with Section 424 of the Standard Specifications, ~~except that shall also include any additional excavation or embankment required to construct the sidewalk as shown in the plans and as directed by the Engineer.~~ Excavated sub-base that is not to be incorporated into the project is to be disposed of off-site in accordance with the applicable portions of Section 202 of the Standard Specifications. Disturbed areas shall be seeded according to the applicable portions of Section 250 of the Standard Specifications, and as directed by the Engineer.

Curbs adjacent to the sidewalk shall be constructed at locations shown in the plans or as directed by the Engineer.

This work shall be paid for at the contract unit price per square foot for PORTLAND CEMENT CONCRETE SIDEWALK of the thickness specified, which price shall include all labor, equipment, and materials necessary to complete the work as shown in the plans and as directed by the Engineer.

CONCRETE SIDEWALK FINISHING: This work applies to concrete sidewalk surfaces within the project limits and consists of finishing concrete as detailed in the plans and as directed by the Engineer.

Submittals:

(a) The following items shall be submitted and approved prior to operations:

1. Proposed concrete mix.

(b) The following items shall be submitted during operations:

1. Concrete load tickets
2. Concrete sample test results.

Products:

- (a) Concrete: Portland cement concrete in compliance with SI in accordance with Section 1020 – Portland Cement Concrete, IDOT Standard Specifications.
- (b) Concrete Sealer: According to Section 1026 – Concrete Sealer, IDOT Standard Specifications.