

MODEL: Default
 FILE: Multi-plot/printers-pw-beitfy.com:primera-pw-01\Documents\01 - Project\2020\20200425.00 - DDOT Phase II Various Design\20200425.01.WD.1.3 - Wolf Road over I-89\Drawings\Current Drawing Files\CADD_Sheets\Roadway\011223\3-ink-500-01.dgn
 300 N. JACKSON BLVD. SUITE 600, CHICAGO, IL 60610 P.312-465-4010 F.312-465-4015

CODE NO.	ITEM	UNIT	TOTAL QUANTITY URBAN	CONSTRUCTION CODE	
				BRIDGE	WOLF RD SN 099-0192
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	150	0013	150
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	25	90% FED	25
20101000	TEMPORARY FENCE	FOOT	100	10% STATE	100
20200100	EARTH EXCAVATION	CU YD	383		383
20400800	FURNISHED EXCAVATION	CU YD	6106		6106
20800150	TRENCH BACKFILL	CU YD	242		242
25003210	INTERSEEDING, CLASS 2A	ACRE	1		1
25100125	MULCH, METHOD 3	ACRE	1		1
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	824		824
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5883		5883
25000210	SEEDING, CLASS 2A	ACRE	0.5		0.5
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	46		46
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	46		46
25100635	HEAVY DUTY EROSION CONTROL BLANKET	SQ YD	2473		2473
28000305	TEMPORARY DITCH CHECKS	FOOT	275		275
28000400	PERIMETER EROSION BARRIER	FOOT	1584		1584
28000500	INLET AND PIPE PROTECTION	EACH	3		3
31200500	STABILIZED SUBBASE - HOT-MIX ASPHALT, 4"	SQ YD	118		118
35101600	AGGREGATE BASE COURSE, TYPE B 4"	SQ YD	3795		3795
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SQ YD	40		40
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	1853		1853
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	5		5
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	170		170
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	529		529
40604060	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N50	TON	5		5
40604062	HOT-MIX ASPHALT SURFACE COURSE, IL-9.5, MIX "D", N70	TON	353		353
42000060	WELDED WIRE REINFORCEMENT	SQ YD	147		147
42000080	PAVEMENT CONNECTOR (PCC) FOR BRIDGE APPROACH SLAB	SQ YD	147		147
42001300	PROTECTIVE COAT	SQ YD	4195		4195
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	34155		34155
42400800	DETECTABLE WARNINGS	SQ FT	200		200
44000100	PAVEMENT REMOVAL	SQ YD	297		297
44000600	SIDEWALK REMOVAL	SQ FT	200		200
44000164	HOT-MIX ASPHALT SURFACE REMOVAL, 3 3/4"	SQ YD	3821		3821
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	75		75
44001980	CONCRETE BARRIER REMOVAL	FOOT	99		99
44004250	PAVED SHOULDER REMOVAL	SQ YD	2148		2148

3



USER NAME = rvandermus	DESIGNED - RM/RMV	REVISED -
DRAWN - RM/RMV	REVISED -	
PLOT SCALE = 2.0000 / in.	CHECKED - MPV	REVISED -
PLOT DATE = 2/4/2022	DATE - 07/07/2021	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES			
WOLF ROAD BRIDGE OVER I-80			
SCALE:	SHEET	OF	SHEETS
		STA.	TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2688	2020-250-BY	WILL	133	3
CONTRACT NO. 62N20				
ILLINOIS FED. AID PROJECT				

3 REVISED SHEET 4/20/2022