



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

April 8, 2022

SUBJECT FAP Route 328 (US 45)
Project NHPP-PMUX(528)
Section 12ZRS-2
Effingham County
Contract No. 74797
Item No. 169, April 29, 2022 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised Schedule of Prices.
2. Revised Table of Contents of the Special Provisions.
3. Revised Page 15 of the Special Provisions.
4. Revised Sheets 7, 90, and 96-98 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

MTS

TABLE OF CONTENTS

LOCATION OF PROJECT 1

DESCRIPTION OF PROJECT 1

WORKING DAY RESTRICTIONS 2

TRAFFIC CONTROL PLAN (FOR TRAFFIC SIGNAL REHABILITATION PROJECTS) 2

ADA CURB RAMPS 3

BORROW AREAS, USE AREAS, AND/OR WASTE AREAS 5

CHANGEABLE MESSAGE SIGNS 5

COMBINATION CONCRETE CURB AND GUTTER, TYPE B (SPECIAL) 6

COMBINATION CURB AND GUTTER REMOVAL (SPECIAL) 6

COORDINATION WITH OTHERS 6

DETOUR SIGNING 6

ELECTRIC CABLE IN CONDUIT 7

HANDHOLE / DOUBLE HANDHOLE 7

HMA SURFACE REMOVAL, VARIABLE DEPTH 7

ISLAND REMOVAL 8

NOTIFICATION OF ROAD CLOSURE 8

PAVEMENT PATCHING STANDARD 442201 8

PEDESTRIAN PUSH-BUTTON POST 9

PEDESTRIAN PUSHBUTTON 9

POLYCARBONATE SIGNAL HEADS 10

PROTECTING OR RESETTING SURVEY MARKERS 10

RELOCATE EXISTING CONFIRMATION BEACON 11

REMOVAL AND DISPOSAL OF REGULATED SUBSTANCES 11

REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT 13

TEMPORARY RAMP, SPECIAL 14

UNDERGROUND CONDUIT 14

UTILITIES 14

ACCESSIBLE PEDESTRIAN SIGNALS 15

ACCESSIBLE PEDESTRIAN SIGNALS (APS) (BDE) 16

BITUMINOUS MATERIALS COST ADJUSTMENTS (BDE) 17


BLENDED FINELY DIVIDED MINERALS (BDE) 18

COMPENSABLE DELAY COSTS (BDE) 19

DISADVANTAGED BUSINESS ENTERPRISE PARTICIPATION (BDE) 22

FUEL COST ADJUSTMENT (BDE) 31

HOT-MIX ASPHALT – PATCHING (BDE) 33



HOT-MIX ASPHALT – START OF PRODUCTION (BDE) 33
PORTLAND CEMENT CONCRETE – HAUL TIME (BDE)..... 34
STEEL COST ADJUSTMENT (BDE)..... 35
SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE) 37
SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE) 38
SURFACE TESTING OF PAVEMENTS – IRI (BDE) 38
VEHICLE AND EQUIPMENT WARNING LIGHTS (BDE) 44
WEEKLY DBE TRUCKING REPORTS (BDE)..... 44
WORK ZONE TRAFFIC CONTROL DEVICES (BDE) 44
WORKING DAYS (BDE) 46

<u>Name/Address of Utility Company</u>	<u>Type</u>	<u>Location of conflict</u>	<u>Est. Date of Relocation</u>
City of Effingham Att: Jeremy Heuerman 201 E. Jefferson Avenue, Effingham, IL 62401 Phone: (217)342-5300 or (217)821-0870	Water	St. Louis Avenue (SW Quad) Water Valve Adjust Virginia Avenue (NW Quad) Water Valve Adjust Temple Avenue (SW Quad) Water Valve Adjust (in removal area)	During Construction



ACCESSIBLE PEDESTRIAN SIGNALS

This work shall consist of furnishing and installing pedestrian pushbuttons of the type specified in accordance with Section 888 and Article 1074.02 of the Standard Specifications and Accessible Pedestrian Signals (APS) (BDE) except as modified herein.

The pushbuttons shall meet ADA requirements. All pedestrian pushbuttons shall have a case and be equipped with a 2" Diameter button for easy access. The push buttons shall have a yellow housing and utilize a solid-state switch or reed relay. The following model is approved within the district: Polara iN2 Navigator 2-wire Push Button Station (iN2PBS) or approved equal.

The pedestrian pushbutton shall be in a modular station assembly accommodating the size of sign listed below (9x15). The pushbutton will be part of the modular station with a four-hole mount round cover assembly.

The pedestrian pushbutton installation shall include all crossing signs and hardware required to mount the pedestrian pushbutton. All hardware shall be of stainless-steel construction. All bolts shall be Hex Head and no self tapping/drilling screws will be allowed. Anti-seize paste shall be installed on all fasteners.

All signs for pedestrian pushbutton shall be MUTCD sign R10-3e. All signs **shall not** be digitally printed.

This work will be paid for at the contract unit price EACH for ACCESSIBLE PEDESTRIAN SIGNALS.

Revised 4-12-2022