

100% STATE

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		I000						CODE NO	ITEM		UNIT				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	60	60													
21101615	TOP SOIL FURNISH AND PLACE, 4"	SQ YD	23	23													
25200110	SODDING, SALT TOLERANT	SQ YD	23	23													
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	7	7													
40600300	AGGREGATE (PRIME COAT)	TON	32	32													
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	12	12													
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), 1L-4.75, N50	TON	314	314													
40600895	CONSTRUCTING TEST STRIP	EACH	2	2													
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	24	24													
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	781	781													
42001300	PROTECTIVE COAT	SQ YD	7	7													
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	100	100													
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	86	86													
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	48	48													
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	60	60													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	775	775													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD T01306	L SUM	1	1													
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD T01336	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	1581	1581													
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	7960	7960													
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	527	527													
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	7960	7960													
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	50	50													
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	50	50													
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52													
X4421000	PARTIAL DEPTH PATCHING	TON	73	73													
X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	434	434													

*Specialty Items

FILE NAME =	USER NAME = wirtchkd	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	U.S. ROUTE 30 (KENDALL CO. LINE TO 0.3 MILE W. OF ALBRIGHT RD.) SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
CONTRACT NO. 60159	349	11-RS-5	KANE			14	3			
SCALE: N/A	SHEET NO.	OF	SHEETS			STA.	TO STA.			
FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT										