

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

INDEX OF SHEETS

S1. General Plan and Section

S2. General Notes, Bill of Materials and Index of Sheets

GENERAL NOTES:

1. Reinforcement bars shall conform to the requirements of ASTM A 706 Grade 60. See Special Provisions.
2. Reinforcement bars designated (E) shall be epoxy coated.
3. Plan dimensions and details relative to existing plans are subject to nominal construction variations. The Contractor shall field verify existing dimensions and details affecting new construction and make necessary approved adjustments prior to construction or ordering of materials. Such variations shall not be cause for additional compensation for a change in scope of the work, however, the Contractor will be paid for the quantity actually furnished at the unit price bid for the work.
4. An assigned detour shall be utilized to maintain traffic during construction.
5. Hot-Mix Asphalt Surface Removal (Deck) will include any PCC Pavement Removal required to achieve 10 inches of surface removal on the areas shown on the Plans. Hot-Mix Asphalt Surface Removal (Deck) shall include removal areas on Approaches.

TOTAL BILL OF MATERIAL

ITEM DESCRIPTION	UNIT	SUPER	SUB	TOTAL
Hot-Mix Asphalt Surface Removal (Deck)	Sq. Yd.	98		98
Reinforcement Bars, Epoxy Coated	Pound	7,850		7,850
Concrete Superstructure	Cu. Yd.	26		26
Protective Coat	Sq. Yd.	93		93
Bridge Deck Grooving	Sq. Yd.	89		89

GENERAL NOTES, BILL OF MATERIALS
AND INDEX OF SHEETS
STRUCTURE NO. 016-1210

DESIGNED <i>JMH</i>	2018
CHECKED <i>JMH</i>	EXAMINED
DRAWN <i>DR</i>	ENGINEER OF STRUCTURAL SERVICES
CHECKED <i>JMH</i>	PASSED
	ENGINEER OF BRIDGES AND STRUCTURES

SHEET NO. S2 OF S2 SHEETS	F.A.P. RTE. 351	SECTION 536T-1	COUNTY COOK	TOTAL SHEETS 8	SHEET NO. 5
			CONTRACT NO. 60I62		
ILLINOIS FED. AID PROJECT					