

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE CONSTRUCTION TYPE CODE						SUMMARY OF QUANTITIES			80% FED. 20% STATE CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES					CODE NO	ITEM	UNIT	TOTAL QUANTITIES						
				I000								I000					
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	200	200				70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1					
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	4	4				70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	4	4				70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	4	4				70300100	SHORT-TERM PAVEMENT MARKING	FOOT	5500	5500					
25200200	SUPPLEMENTAL WATERING	UNIT	10	10				70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	250	250					
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	25	25				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15000	15000					
40600300	AGGREGATE (PRIME COAT)	TON	185	185				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	330	330					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	27	27				70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	210	210					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1100	1100				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	200	200					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	200	200					
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	160	160				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3000	3000					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	2167	2167				78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	330	330					
42001300	PROTECTIVE COAT	SO YD	275	275				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15000	15000					
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	1200	1200				* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	330	330					
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	25300	25300				* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	210	210					
44000600	SIDEWALK REMOVAL	SO FT	1200	1200				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	200	200					
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	800	800				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	200	200					
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1100	1100				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	500	500					
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	200	200				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	420	420					
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	650	650				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	1020	1020					
55039700	STORM SEWERS TO BE CLEANED	FOOT	500	500				X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
60250200	CATCH BASINS TO BE ADJUSTED	EACH	14	14				Δ Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	10	10					
60300205	FRAMES AND GRATES TO BE ADJUSTED (SPECIAL)	EACH	30	30													
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	1	1													
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	2	2													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1													
70100600	TRAFFIC CONTROL AND PROTECTION, STANDARD 701336	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													

Δ Non-participating
*Specialty Items