

INDEX OF SHEETS		STATE STANDARDS		GENERAL NOTES	
SHEET NO.	DESCRIPTION				
1	COVER SHEET	000001- <del>05</del>	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS	<p>BEFORE STARTING ANY EXCAVATION THE CONTRACTOR SHALL CALL "JULIE" AT 800-892-0123 OR "CUAN" (CHICAGO UTILITY ALERT NETWORK) AT 312-744-7000 FOR FIELD LOCATIONS OF BURIED ELECTRIC, TELEPHONE AND GAS FACILITIES, (48 HOURS NOTIFICATION IS REQUIRED).</p> <p>10 FEET (3 METERS) TRANSITIONS SHALL BE USED TO MATCH PROPOSED CURB AND GUTTER AND MEDIAN ITEMS OF WORK TO EXISTING CURBS AND GUTTERS AND MEDIANS IN THE FIELD, UNLESS OTHERWISE SHOWN. THE TRANSITION SHALL BE PAID FOR AT THE CONTRACT UNIT PRICE FOR THE PROPOSED ITEMS OF WORK SPECIFIED.</p> <p>THE CONTRACTOR SHALL COORDINATE CONSTRUCTION ACTIVITIES WITH THE UTILITY COMPANIES AND THE VILLAGE OF SCHILLER PARK.</p> <p>THE CONTRACTOR WILL NOT BE ALLOWED TO SET UP A YARD OR FIELD OFFICE ON STATE PROPERTY WITHOUT WRITTEN PERMISSION FROM THE DEPARTMENT.</p> <p>THE CONTRACTOR SHALL CONTRACT THE DISTRICT ONE TRAFFIC CONTROL SUPERVISOR CORY JUCIUS AT (847) 705-4470 A MINIMUM OF 72 HOURS PRIOR TO START OF WORK.</p> <p>WHEN MILLED PAVEMENT IS OPEN TO TRAFFIC THE MAXIMUM GRADE DIFFERENTIAL BETWEEN PASSES OF THE MILLING MACHINE SHALL NOT EXCEED 1½INCHES (40MM) WHERE THE SPEED LIMIT IS 45 MPH (80 KM/H). WITH WRITEN APPROVAL FROM THE ENGINEER, A MAXIMUM GRADE DIFFERENTIAL OF 3 INCHES (75MM) MAY BE ALLOWED IF THE EDGE OF THE MILLING IS SLOPED A MINIMUM 1:3 (V:H)</p> <p>BUTT JOINTS WILL BE INSTALLED AT THE ENDS OF ALL RESURFACING (WHERE RESURFACING MEETS EXISTING PAVEMENT), IN ACCORDANCE WITH THE "BUTT JOINT AND HMA TAPER DETAILS" SHEET INCLUDED IN THE PLANS, UNLESS OTHERWISE SPECIFIED.</p> <p>PERMANENT PAVEMENT MARKINGS SHALL BE THERMOPLASTIC (OF THE EXTRUDED TYPE) AND SHOULD BE PLACED IN ACCORDANCE "DISTRICT ONE TYPICAL PAVEMENT MARKINGS".</p> <p>RAISED REFLECTIVE PAVEMENT MARKERS SHALL BE IN ACCORDANCE WITH THE DISTRICT ONE "TYPICAL APPLICATION RAISED REFLECTIVE PAVEMENT MARKERS" DETAIL.</p> <p>THE RESIDENT ENGINEER SHOULD CONTACT MR. WALLY CZARNY, AREA TRAFFIC ENGINEER, AT (773) 685-4342 PRIOR TO PLACING ANY PAVEMENT MARKINGS.</p>	
2	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES	442201- <del>03</del>	CLASS C AND D PATCHES		
3	SUMMARY OF QUANTITIES	604011- <del>04</del>	FRAME AND LIDS, TYPE 1		
4-5	EXISTING AND PROPOSED TYPICAL SECTIONS	606001- <del>04</del>	CONCRETE CURB AND COMBINATION CONCRETE CURB AND GUTTER		
6	ROADWAY AND PAVEMENT MARKING PLANS	701601- <del>06</del>	URBAN LANE CLOSURE, MULTILANE 1W OR 2W WITH NON-TRANSVERSABLE MEDIAN		
7	DETAILS FOR FRAMES AND LIDS ADJUSTMENT WITH MILLING	701606- <del>06</del>	URBAN LANE CLOSURE, MULTILANE 2-W WITH MOUNTABLE MEDIAN		
8	PAVEMENT PATCHING FOR HMA SURFACED PAVEMENT	701701- <del>06</del>	URBAN LANE CLOSURE, MULTILANE INTERSECTION		
9	CURB OR CURB AND GUTTER REMOVAL AND REPLACEMENT	701801- <del>04</del>	LANE CLOSURE, MULTILANE, 1W OR 2W, CROSSWALK OR SIDEWALK CLOSURE		
10	BUTT JOINT AND HMA TAPER DETAILS	701901- <del>01</del>	TRAFFIC CONTROL DEVICES		
11	TRAFFIC CONTROL AND PROTECTION FOR SIDE ROADS, INTERSECTIONS, AND DRIVEWAYS	780001- <del>02</del>	TYPICAL PAVEMENT MARKINGS		
12	TYPICAL APPLICATIONS FOR RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT)	781001- <del>03</del>	TYPICAL APPLICATION RAISED REFLECTIVE PAVEMENT MARKERS		
13	DISTRICT ONE TYPICAL PAVEMENT MARKING	886001- <del>01</del>	DECTECTOR LOOP INSTALLATIONS		
14	TRAFFIC CONTROL AND PROTECTION AT TURN BAYS (TO REMAIN OPEN TO TRAFFIC)	886006- <del>01</del>	TYPICAL LAYOUT FOR DETECTION LOOPS		
15	TEMPORARY PAVEMENT MARKING--LETTERS AND SYMBOLS FOR TRAFFIC STAGING				
16-21	STANDARD TRAFFIC SIGNAL DESIGN DETAILS				
22	DETECTOR LOOP INSTALLATION DETAILS FOR ROADWAY RESURFACING				
23-24	DETECTOR LOOP LOCATION DETAILS				
25	ARTERIAL ROAD INFORMATION SIGNING				

FILE NAME =		USER NAME = steadpa	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, STATE STANDARDS, AND GENERAL NOTES FAU 1362 (LAWRENCE AVE.)--FORSTER AVE. TO EAST RIVER RD.		F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
c:\pw\work\pwidot\steadpa\ad0169821\01177		0-shit-planudgn	DRAWN -	REVISED -		1362	3200 RS-3	COOK	25	2		
PLOT SCALE = 50.0000' / IN.		CHECKED -	REVISED -					CONTRACT NO. 60J07				
PLOT DATE = 1/22/2018		DATE -	REVISED -			SCALE: SHEET NO. OF SHEETS STA. TO STA.		FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT				