

SUMMARY OF QUANTITIES			90% FEDERAL, 10% STATE			SUMMARY OF QUANTITIES			90% FEDERAL, 10% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X321-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000-2A	BRIDGE X321-2A
20201006	GRADING AND SHAPING SHOULDERS	UNIT	3	3		51100100	SLOPE WALL 4"	SQ YD	247		247
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	2	2		51205210	TEMPORARY SHEET PILING	SQ FT	232		232
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	208	208		51500200	RELOCATING NAME PLATES	EACH	2		2
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	83	83		52000110	PREFORMED JOINT STRIP SEAL	FOOT	184		184
40600400	MIXTURE FOR CRACK, JOINTS AND FLANGWAYS	TON	2	2		52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	14		14
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	1	1		52100020	ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	14		14
40600635	LEVELING BINDER (MACHNE METHOD), N70	TON	43	43		52100520	ANCHOR BOLTS, 1"	EACH	112		112
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	100	100		59300100	CONTROLLED LOW-STRENGTH MATERIAL	CU YD	81.9		81.9
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	369	369		* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	320	320	
44000198	HOT-MIX ASPHALT SURFACE REMOVAL, VARIABLE DEPTH	SQ YD	563	563		* 63100085	TRAFFIC BARRIER TERMINAL, TYPE 6	EACH	6	6	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	5	5		67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	9	9	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	1369		1369	* 63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2	2	
44201974	CLASS D PATCHES, TYPE 1	SQ YD	5	5		63200310	GUARDRAIL REMOVAL	FOOT	720	720	
48100100	AGGREGATE SHOULDER, TYPE A	TON	1	1		67100100	MOBILIZATION	L SUM	1	1	
50102400	CONCRETE REMOVAL	CU YD	27.3		27.3	64200105	SHOULDER RUMBLE STRIP	FOOT	2,700	2,700	
50104000	BRIDGE RAIL REMOVAL	FOOT	683		683	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	6	6	
50104650	SLOPE WALL REMOVAL	SQ YD	247		247	70300240	TEMPORARY PAVEMENT MARKING, LINE 6"	FOOT	700	700	
50157300	PROTECTIVE SHIELD	SQ YD	470		470	70400100	TEMPORARY CONCRETE BARRIER	FOOT	700	700	
50300225	CONCRETE STRUCTURES	CU YD	2		2	70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	700	700	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	40.7		40.7	* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	23,420	22528	892
50300260	BRIDGE DECK GROOVING	SQ YD	1293		1293	* 78000300	THERMOPLASTIC PAVEMENT MARKING-LINE 5"	FOOT	1130	1050	80
50300300	PROTECTIVE COAT	SQ YD	1490		1490	* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 8"	FOOT	1396	1396	
50300530	FLOOR DRAIN EXTENSION	EACH	40		40	78000210	POLYUREA PAVEMENT MARKING-TYPE 1-LINE 4"	FOOT	892		892
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	LBS	3210		3210	* 78000600	THERMOPLASTIC PAVEMENT MARKING-LINE 12"	FOOT	409	409	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	28		28	78000220	POLYUREA PAVEMENT MARKING-TYPE 1-LINE 5"	FOOT	80		80
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	8170		8170	* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	8	8	
50800515	BAR SPLICERS	EACH	52		52	* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8		8

* SPECIALTY ITEMS

LONGO, INC.
CONSULTING ENGINEERS
1560 WALL ST., SUITE 222
NAPERVILLE, ILLINOIS 60563 PH: (630) 577-9100

DESIGNED - MJY	REVISED -
DRAWN - ST, TSC	REVISED -
CHECKED - MJY, DC	REVISED -
DATE - 1/29/2010	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
I-57 NB & SB OVER ABANDONED RR (12.8 MILES SOUTH OF US 30)

SCALE: NONE SHEET NO. 3 OF 38 SHEETS STA. 939+74 TO STA. 943+21

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	99-2VB-I-1	WILL	38	3
D-91-215-10		CONTRACT NO. 60J25		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

Rev.