

URBAN
80% FED.
20% STATE

SUMMARY OF QUANTITIES

URBAN
80% FED.
20% STATE

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X243-2A STRUCTURE	1000-2A ROADWAY
20200100	EARTH EXCAVATION	CU YD	532		532
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	451	33	418
40600625	LEVELING BINDER (MACHINE METHOD), N50	TON	7	7	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	19	19	
42001300	PROTECTIVE COAT	SQ YD	120		120
44000156	HOT-MIX ASPHALT SURFACE REMOVAL, 1 3/4"	SQ YD	107	107	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	760	760	
48101600	AGGREGATE SHOULDER, TYPE B, 8"	SQ YD	597		597
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	597		597
50102400	CONCRETE REMOVAL	CU YD	9.7	9.7	
50157301	PROTECTIVE SHIELD (PERMANENT)	SQ YD	400	400	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	9.6	9.6	
50300260	BRIDGE DECK GROOVING	SQ YD	726	726	
50300300	PROTECTIVE COAT	SQ YD	795	795	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	1990	1990	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	12	12	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	1320	1320	
50800515	BAR SPLICERS	EACH	16	16	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	85	85	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12	12	
52100520	ANCHOR BOLTS, 1"	EACH	24	24	
58700300	CONCRETE SEALER	SQ FT	3670	3670	
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	756		756
63300115	REMOVAL AND REINSTALLATION OF EXIST'NG STEEL PLATE BEAM GUARD RAIL, SINGLE RAIL	FOOT	825		825
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3		3
67100100	MOBILIZATION	L SUM	1		1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1		1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20		20
70106500	TEMPORARY BRIDGE TRAFFIC SIGNALS	EACH	1		1
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	3		3
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	904		904
70400100	TEMPORARY CONCRETE BARRIER	FOOT	462.5		462.5
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	462.5		462.5
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1084		1084
* 78000210	EPOXY POLYUREA PAVEMENT MARKING - LINE 4"	FOOT	2264		2264
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	29		29

CODE NUMBER	ITEM	UNIT	TOTAL QUANTITY	X243-2A STRUCTURE	1000-2A ROADWAY
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	14		14
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	148		148
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1116		1116
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	43		43
X0322185	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/4 INCHES	SQ YD	760	760	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	116		116
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	111	111	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	88	88	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	2448		2448
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	48		48
X0326276	TEMPORARY LIGHTING FOR SINGLE LANE STAGING	L SUM	1		1
X0326766	CLEAN & RE SEAL RELIEF JOINT	FOOT	82	82	
X7011015	TRAFFIC CONTROL AND PROTECTION, (EXPRESSWAYS)	L SUM	1		1
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	10		10
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	8.2	8.2	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	760	760	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2		2
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2		2
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	35.8	35.8	

*Specialty Items

FILE NAME =
#FILE#

USER NAME = #USER#
PLOT SCALE = #SCALE#
PLOT DATE = #DATE#

DESIGNED - SEW
DRAWN - SEW
CHECKED - FML
DATE - 1/2010

REVISED -
REVISED -
REVISED -
REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES
FLOSSMOOR ROAD OVER I-57

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
57	0607-1007 HB-1	COOK	29	3

CONTRACT NO. 60J26
ILLINOIS FED. AID PROJECT

Rev.