

SUMMARY OF QUANTITIES				URBAN 90% FED. 10% STATE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	010-2039 SFTY-2A QUANTITY	
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	14	14	
42001300	PROTECTIVE COAT	SQ YD	397	397	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	115	115	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	368	368	
50157301	PROTECTIVE SHIELD (PERMANENT)	SQ YD	514	514	
50300260	BRIDGE DECK GROOVING	SQ YD	368	368	
59000200	EPOXY CRACK INJECTION	FOOT	24	24	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	623	623	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	200	200	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	200	200	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	422	422	
* 78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	129	129	

SUMMARY OF QUANTITIES				URBAN 90% FED. 10% STATE	CONSTRUCTION TYPE CODE
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	010-2039 SFTY-2A QUANTITY	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	184	184	
X0320887	POLYMER CONCRETE	CU FT	7	7	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	368	368	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	
X0322276	CLEANING AND PAINTING EXPOSED REBAR	L SUM	1	1	
X0323076	SILICONE JOINT SEALER, 1 3/4"	FOOT	127	127	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	259	259	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	1580	1580	
X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	48	48	
X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1	
X7013820	TRAFFIC CONTROL SURVEILLANCE, EXPRESSWAYS	CAL DA	20	20	
X8900005	TEMPORARY BRIDGE TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	368	368	
Z0016002	DECK SLAB REPAIR (FULL DEPTH TYPE II)	SQ YD	5	5	
Z0030260	IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3	EACH	2	2	
Z0030330	IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

* Specialty Items