



208 FT. CONCRETE MEDIAN REMOVAL (PRIOR TO STAGE 1)
 92 SQ. YD. HMA BASE COURSE, 8 1/4"
 92 SQ. YD. PAVEMENT REMOVAL
 831 SQ. FT. CONCRETE MEDIAN, TYPE SB-6.06
 (SEE NOTE 4)

20 LF COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT
 PROJECT LIMIT STA. 8+43.83

20 LF COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

20 LF COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT

PROJECT LIMIT STA. 11+50.43

47 SQ. YD. * CLASS B PATCHES, TYPE IV, 8 INCH
 60 SQ. YD. * CLASS B PATCHES, TYPE IV, 12 INCH

214 FT. CONCRETE MEDIAN REMOVAL (PRIOR TO STAGE 1)
 95 SQ. YD. HMA BASE COURSE, 8 1/4"
 95 SQ. YD. PAVEMENT REMOVAL
 856 SQ. FT. CONCRETE MEDIAN, TYPE SB-6.06
 (SEE NOTE 4)

LEGEND:

- ① POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (WHITE EDGE LINE)
- ② POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (YELLOW EDGE LINE)
- ③ POLYUREA PAVEMENT MARKING TYPE 1 - LINE 4" (WHITE, 10' DASH, 30' SKIP)
- ④ POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8" (WHITE GORE LINE)
- ⑤ POLYUREA PAVEMENT MARKING TYPE 1 - LINE 8" (WHITE, 3' DASH, 9' SKIP)
- ⑥ RAISED REFLECTIVE MARKERS
- ⑦ RAISED REFLECTIVE MARKERS (BRIDGE)

NOTES:

1. SEE IDOT DISTRICT 1 STANDARD TC-11 "RAISED REFLECTIVE PAVEMENT MARKERS (SNOW PLOW RESISTANT)" FOR PLACEMENT AND TYPE OF RAISED REFLECTIVE PAVEMENT MARKERS.
 2. SEE IDOT DISTRICT 1 STANDARD TC-13 "DISTRICT ONE TYPICAL PAVEMENT MARKINGS" FOR ADDITIONAL PAVEMENT MARKING INFORMATION.
 3. COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT SHOULD BE CONSTRUCTED SO GUTTER ELEVATION MATCHES PROPOSED OVERLAY PAVEMENT ELEVATION AND TOP OF CURB ELEVATION MATCHES ADJACENT SIDEWALK ELEVATION.
 4. #6 EPOXY COATED TIE BARS @ 24" C-C, 24" LONG, DRILLED AND GROUTED (INCLUDED IN THE COST OF "CONCRETE MEDIAN, TYPE SB-6.06").
- * EXACT AREA FOR PATCHES TO BE DETERMINED IN THE FIELD BY THE ENGINEER. ACTUAL DEPTH OF PATCHES ARE 8 1/4" FOR WILLOW ROAD LANES AND 12 1/4" FOR RAMP, TO BE PAID FOR AS CLASS B PATCHES, TYPE IV, 8 INCH AND 12 INCH, RESPECTIVELY.

FILE NAME =	DESIGNED - EJA	REVISED -
	DRAWN - EJA	REVISED -
USER NAME =	CHECKED - AJP	REVISED -
PLOT DATE = 03/22/2010	DATE - 3/19/10	REVISED -

benesch

**STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION**

**WILLOW ROAD
 ROADWAY & PAVEMENT MARKING PLANS**
 SCALE: 1" = 30" SHEET NO. 1 OF 1 SHEETS STA. TO STA.

F.A.I. RTE. 94	SECTION 1010.1-1-2	COUNTY COOK	TOTAL SHEETS 37	SHEET NO. 8
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 60J30				