

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	016-0928 SFTY-2A QUANTITY	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	29	29	
42001300	PROTECTIVE COAT	SQ YD	434	434	
44000100	PAVEMENT REMOVAL	SQ YD	96	96	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	248	248	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	405	405	
44003100	MEDIAN REMOVAL	SQ FT	860	860	
50102400	CONCRETE REMOVAL	CU YD	22	22	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	25	25	
50300260	BRIDGE DECK GROOVING	SQ YD	401	401	
50500405	FURNISHING AND ERECTING STRUCTURAL STEEL	POUND	5080	5080	
50500715	JACK AND REMOVE EXISTING BEARINGS	EACH	16	16	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2280	2280	
50800515	BAR SPLICERS	EACH	32	32	
52000110	PREFORMED JOINT STRIP SEAL	FOOT	157	157	
52100010	ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	16	16	
52100520	ANCHOR BOLTS, 1"	EACH	32	32	
60619600	CONCRETE MEDIAN, TYPE SB-6.12	SQFT	860	860	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	016-0928 SFTY-2A QUANTITY	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1862	1862	
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	37	37	
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	2215	2215	
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	285	285	
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	36	36	
* 78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16	16	
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	88	88	
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	886	886	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	92	92	
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1	1	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	405	405	
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	96	96	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	45	45	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	13	13	
X0325737	TEMPORARY TRAFFIC SIGNAL TIMING	EACH	1	1	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	5085	5085	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	405	405	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	51	51	
88600100	DETECTOR LOOP TYPE I	FOOT	66	66	
50501110	STRUCTURAL STEEL REMOVAL	POUND	660	660	
89502200	MODIFY EXISTING CONTROLLER	EACH	1	1	

FILE NAME =
FILE



DESIGNED	VEA	REVISED	-
DRAWN	VEA	REVISED	-
CHECKED	TWL	REVISED	-
DATE	1/29/2010	REVISED	-

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
376	2009-116-1	COOK	23	3
CONTRACT NO. 60J41				
ILLINOIS FED. AID PROJECT				

Rev.