

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	016-0286 SFTY-2A QUANTITY	
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5 ^{FG} , N70	TON	12	12	
20200100	EARTH EXCAVATION	CU YD	545	545	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	13	13	
42001300	PROTECTIVE COAT	SQ YD	218	218	
44000100	PAVEMENT REMOVAL	SQ YD	2012	2012	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	144	144	
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	2175	2175	
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	154	154	
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	13,868	13,868	
50102400	CONCRETE REMOVAL	CU YD	14	14	
50300255	CONCRETE SUPERSTRUCTURE	CU YD	14	14	
50300260	BRIDGE DECK GROOVING	SQ YD	201	201	
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	2650	2650	
60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	2	2	
60605900	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-9.12	FOOT	2175	2175	
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SQ FT	13,868	13,868	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3	
67100100	MOBILIZATION	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10	
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3052	3052	

SUMMARY OF QUANTITIES			URBAN 80% FED. 20% STATE	CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	016-0286 SFTY-2A QUANTITY	
70400100	TEMPORARY CONCRETE BARRIER	FOOT	280	280	
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	210	210	
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3026	3026	
*78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	14	14	
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	86	86	
*78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	- EACH	4	4	
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1022	1022	
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	90	90	
X0320887	POLYMER CONCRETE	CU FT	7	7	
X0322489	BRIDGE DECK LATEX CONCRETE OVERLAY, 2 1/2 INCHES	SQ YD	213	213	
X0325239	TEMPORARY PAVEMENT 10"	SQ YD	2012	2012	
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51	
X0322276	CLEANING AND PAINTING EXPOSED REBAR	L SUM	1	1	
X0325303	STRUCTURAL REPAIR OF CONCRETE (DEPTH GREATER THAN 5 INCHES)	SQ FT	83	83	
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	54	54	
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	9185	9185	
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	213	213	
Z0016002	DECK SLAB REPAIR (FULL DEPTH, TYPE II)	SQ YD	9	9	
Z0018700	DRAINAGE STRUCTURE TO BE REMOVED	EACH	2	2	
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2	

*Specialty Items

Rev.