

| SUMMARY OF QUANTITIES | | | 80% FED. 20% STATE TOTAL QUANTITY | CONSTRUCTION TYPE CODE | |
|-----------------------|--|------------------|--|---------------------------------|--|
| CODE NO. | ITEM DESCRIPTION | UNIT | | 022-0148 SFTY-2A QUANTITY | |
| 40603595 | POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90 | TON | 22 | 22 | |
| 42001300 | PROTECTIVE COAT | SQ YD | 578 | 578 | |
| 44000157 | HOT-MIX ASPHALT SURFACE REMOVAL, 2" | SQ YD | 254 | 254 | |
| 44000100 | PAVEMENT REMOVAL | SQ YD | 24 | 24 | |
| | BRIDGE DECK OVERLAY REMOVAL | SQ YD | 249 | 249 | |
| 50102400 | CONCRETE REMOVAL | CU YD | 44 | 44 | |
| 50300255 | CONCRETE SUPERSTRUCTURE | CU YD | 46 | 46 | |
| 50800205 | REINFORCEMENT BARS, EPOXY COATED | POUND | 9750 | 9750 | |
| 67000400 | ENGINEER'S FIELD OFFICE, TYPE A | CAL MO | 3 | 3 | |
| 67100100 | MOBILIZATION | L SUM | 1 | 1 | |
| 70101800 | TRAFFIC CONTROL AND PROTECTION, (SPECIAL) | L SUM | 1 | 1 | |
| 70103815 | TRAFFIC CONTROL SURVEILLANCE | CAL DA | 20 | 20 | |
| 70106800 | CHANGEABLE MESSAGE SIGN | CAL MO | 10 | 10 | |
| 70301000 | WORK ZONE PAVEMENT MARKING REMOVAL | SQ FT | 2027 | 2027 | |
| 70400100 | TEMPORARY CONCRETE BARRIER | FOOT | 610 | 610 | |
| 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | FOOT | 500 | 500 | |
| *78000100 | THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS | SQ FT | 73 | 73 | |
| *78000200 | THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 2311 | 2311 | |
| *78000400 | THERMOPLASTIC PAVEMENT MARKING - LINE 6" | FOOT | 200 | 200 | |
| *78000600 | THERMOPLASTIC PAVEMENT MARKING - LINE 12" | FOOT | 78 | 78 | |
| *78006110 | PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4" | FOOT | 392 | 392 | |

| SUMMARY OF QUANTITIES | | | 80% FED. 20% STATE TOTAL QUANTITY | CONSTRUCTION TYPE CODE | |
|-----------------------|--|------------------|--|---------------------------------|--|
| CODE NO. | ITEM DESCRIPTION | UNIT | | 022-0148 SFTY-2A QUANTITY | |
| *78100100 | RAISED REFLECTIVE PAVEMENT MARKER | EACH | 77 | 77 | |
| *78100105 | RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE) | EACH | 6 | 6 | |
| 78300100 | PAVEMENT MARKING REMOVAL | SQ FT | 1152 | 1152 | |
| 78300200 | RAISED REFLECTIVE PAVEMENT MARKER REMOVAL | EACH | 83 | 83 | |
| X0322256 | TEMPORARY INFORMATION SIGNING | SQ FT | 51 | 51 | |
| X0322276 | CLEANING AND PAINTING EXPOSED REBAR | L SUM | 1 | 1 | |
| X0322944 | BRIDGE DECK THIN POLYMER OVERLAY 3/8" | SQ YD | 565 | 565 | |
| X0325305 | STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES) | SQ FT | 121 | 121 | |
| X0325775 | WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH | FOOT | 6080 | 6080 | |
| X0326766 | CLEAN & RESEAL RELIEF JOINT | FOOT | 114 | 114 | |
| 44004600 | SIDEWALK REMOVAL AND REPLACEMENT | SQ FT | 304 | 304 | |
| 44001700 | COMBINATION CURB AND GUTTER REMOVAL AND REPLACEMENT | FOOT | 69 | 69 | |
| Z0001800 | APPROACH SLAB REPAIR (PARTIAL DEPTH) | SQ YD | 42 | 42 | |
| Z0016001 | DECK SLAB REPAIR (FULL DEPTH, TYPE I) | SQ YD | 4 | 4 | |
| Z0016002 | DECK SLAB REPAIR (FULL DEPTH, TYPE II) | SQ YD | 18 | 18 | |
| Z0030250 | IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 2 | 2 | |
| Z0030350 | IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3 | EACH | 4 | 4 | |
| X0326346 | BRIDGE DECK LATEX CONCRETE OVERLAY, 3 INCHES | SQ YD | 250 | 250 | |
| Z0006199 | BRIDGE DECK HYDRO-SCARIFICATION 3/8" | SQ YD | 249 | 249 | |
| Z0006229 | BRIDGE DECK HYDRO-SCARIFICATION 3" | SQ YD | 249 | 249 | |
| X0320887 | POLYMER CONCRETE | CU FT | 4.0 | 4.0 | |

*SPECIALTY ITEMS