

SUMMARY OF QUANTITIES			80% FED. 20% STATE			SUMMARY OF QUANTITIES			80% FED. 20% STATE		
CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X020-2A	CODE NO.	ITEM	UNIT	URBAN TOTAL	ROADWAY 1000	BRIDGE X020-2A
28100807	STONE DUMPED RIPRAP, CLASS A4	TON	50		50	X0322944	BRIDGE DECK THIN POLYMER OVERLAY 3/8"	SQ YD	284		284
28200200	FILTER FABRIC	SQ YD	60		60	X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	7110	7110	
50300300	PROTECTIVE COAT	SQ YD	362		362	X0325841	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 24 INCH	FOOT	144	144	
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		X0325842	WET REFLECTIVE TEMPORARY TAPE, TYPE III, LETTERS AND SYMBOLS	SQ FT	368	368	
67100100	MOBILIZATION	L SUM	1	1		Z0013798	CONSTRUCTION LAYOUT	L SUM	1	1	
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1		Z0030240	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 2	EACH	2	2	
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	6	6		Z0030340	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 2	EACH	4	4	
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	4	4							
70400100	TEMPORARY CONCRETE BARRIER	FOOT	469	469							
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	938	938							
* 78000100	THERMOPLASTIC PAVEMENT MARKING-LETTERS AND SYMBOLS	SQ FT	123	123							
* 78000200	THERMOPLASTIC PAVEMENT MARKING-LINE 4"	FOOT	4085	3829	256						
* 78000650	THERMOPLASTIC PAVEMENT MARKING-LINE 24"	FOOT	48	48							
* <del>78008210</del>	<del>POLYUREA PAVEMENT MARKING TYPE I LINE 4"</del>	<del>FOOT</del>	<del>256</del>		<del>256</del>						
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8		8						
* 78200530	BARRIER WALL MARKERS, TYPE C	EACH	38	38							
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1494	1494							
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	8		8						
X0320532	CONCRETE BRIDGE DECK SCARIFICATION (3/8 INCH)	SQ YD	284		284						
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	52	52							

\* SPECIALTY ITEMS

**LONCO, INC.**  
CONSULTING ENGINEERS  
1560 WALL ST, SUITE 222  
NAPERVILLE, ILLINOIS 60563 PH 630/577-9100

DESIGNED - MJY	REVISED -
DRAWN - SLV	REVISED -
CHECKED - MJY, DC	REVISED -
DATE - 01/29/2010	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES  
IL ROUTE 25 OVER POPLAR CREEK**

SCALE: NONE SHEET NO. 3 OF 18 SHEETS STA. 365+14.15 TO STA. 365+68.01

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
360	49 B-1	KANE	18	3
D-91-237-10			CONTRACT NO. 60J47	
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		