

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	016-0558 SFTY-2A QUANTITY
40600637	LEVELING BINDER (MACHINE METHOD), IL-9.5 <sup>FG</sup> , N70	TON	21	21
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	21	21
42001300	PROTECTIVE COAT	SQ YD	138	138
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SQ YD	240	240
44000915	HOT-MIX ASPHALT SURFACE REMOVAL (DECK)	SQ YD	138	138
50300260	BRIDGE DECK GROOVING	SQ YD	133	133
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3
67100100	MOBILIZATION	L SUM	1	1
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	20	20
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	10	10
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1595	1595
70400100	TEMPORARY CONCRETE BARRIER	FOOT	260	260
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	260	260
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3473	3473

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE	
CODE NO.	ITEM DESCRIPTION	UNIT	URBAN TOTAL QUANTITY	016-0558 SFTY-2A QUANTITY
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	136	136
* 78006110	PREFORMED THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	58	58
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	84	84
* 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	12	12
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1313	1313
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	96	96
X0320887	POLYMER CONCRETE	CUFT	7	7
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51	51
X0325305	STRUCTURAL REPAIR OF CONCRETE (DEPTH EQUAL TO OR LESS THAN 5 INCHES)	SQ FT	54	54
X0325775	WET REFLECTIVE TEMPORARY TAPE, TYPE III, 4 INCH	FOOT	5085	5085
X0326346	BRIDGE DECK LATEX CONCRETE OVERLAY, 3 INCHES	SQ YD	138	138
Z0001800	APPROACH SLAB REPAIR (PARTIAL DEPTH)	SQ YD	5	5
Z0006204	BRIDGE DECK HYDRO-SCARIFICATION 1/2"	SQ YD	138	138
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	2	2