

SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				URBAN CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES 100% STATE	1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	190	190					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	21989	21989				
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	130	130					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	885	885				
21400100	GRADING AND SHAPING DITCHES	FOOT	600	600					78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	21989	21989				
35101400	AGGREGATE BASE COURSE, TYPE B	TON	1295	1295					78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	124	124				
35102000	AGGREGATE BASE COURSE, TYPE B 8"	SO YD	711	711					* 78200420	GUARDRAIL MARKERS, TYPE B	EACH	2	2				
35501308	HOT-MIX ASPHALT BASE COURSE, 6"	SO YD	167	167					* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	2	2				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	19	19					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	80	80				
40600300	AGGREGATE (PRIME COAT)	TON	92	92					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	35	35					X0326861	PULVERIZATION	SO YD	21394	21394				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1					21101615	TOPSOIL FURNISH AND PLACE 4"	SQ YD	1800	1800				
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	5319	5319					25000210	SEEDING, CLASS 2A	ACRE	0.4	0.4				
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	80	80					25000400	NITROGEN FERTILIZER NUTRIENT	POUND	34	34				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1920	1920					25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	34	34				
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	134	134					25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	34	34				
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1736	1736					25100030	EROSION CONTROL BLANKET	SQ YD	1800	1800				
48203015	HOT-MIX ASPHALT SHOULDERS, 4 1/2"	SO YD	35	35													
50105220	PIPE CULVERT REMOVAL	FOOT	160	160													
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"	EACH	2	2													
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	8	8													
54247110	GRATING FOR CONCRETE FLARED END SECTION 18"	EACH	8	8													
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	20	20													
542A0223	PIPE CULVERTS, CLASS A, TYPE 1 18"	FOOT	140	140													
* 63000001	STEEL PLATE BEAM GUARDRAIL, TYPE A, 6 FOOT POSTS	FOOT	130	130													
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2													
63200310	GUARDRAIL REMOVAL	FOOT	26	26													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	2654	2654													

* DENOTES SPECIALTY ITEM

Rev