

SUMMARY OF QUANTITIES				URBAN 100% STATE CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				URBAN 100% STATE CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000					CODE NO	ITEM	UNIT	TOTAL QUANTITIES	1000				
20201006	GRADING AND SHAPING SHOULDERS	UNIT	45	45					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	208	208				
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	12	12					70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15684	15684				
25200110	SODDING, SALT TOLERANT	SO YD	12	12					70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	653	653				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	14	14					70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	458	458				
40600300	AGGREGATE (PRIME COAT)	TON	68	68					70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	310	310				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	25	25					* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	208	208				
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	735	735					* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	15684	15684				
40600895	CONSTRUCTING TEST STRIP	EACH	2	2					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	653	653				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	106	106					* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	458	458				
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	253	253					* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	132	132				
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	35	35					78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100				
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	1485	1485					* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	169	169				
42001300	PROTECTIVE COAT	SO YD	17	17					X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4				
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	11991	11991					X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	844	844				
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	74	74					Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	6	6				
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SO YD	200	200													
44003510	MEDIAN REMOVAL PARTIAL DEPTH	SO FT	3145	3145													
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	173	173													
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	48	48													
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	75	75													
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	90	90													
55039700	STORM SEWERS TO BE CLEANED	FOOT	730	730													
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4													
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	3	3													
60404950	FRAMES AND GRATES, TYPE 24	EACH	2	2													
60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	2	2													
60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	1	1													
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6													
67100100	MOBILIZATION	L SUM	1	1													
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD T01501	L SUM	1	1													
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	929	929													

\* SPECIALTY ITEMS