





Restoration of Work Area. Restoration of the traffic signal work area shall be incidental to the related pay items such as foundation, conduit, handhole, trench and backfill, etc., and no extra compensation shall be allowed. All roadway surfaces such as shoulders, medians, sidewalks, pavement, etc. shall be replaced in kind. All damage to mowed lawns shall be replaced with an approved sod, and all damage to unmowed fields shall be seeded in accordance with Standard Specifications 252 and 250 respectively.

THE TRAFFIC SIGNAL CONTROL EQUIPMENT FOR THIS PROJECT SHALL BE "NTCIP" COMPLIANT.

GHA #4085.859

FILE NAME =	USER NAME = GHA	DESIGNED - JRD	REVISED -
4085.859-TR1.dwg		DRAWN - ZCW	REVISED -
	PLOT SCALE = 1" = .0833"	CHECKED - DPB	REVISED -
	PLOT DATE == 1/27/10	DATE - 1/27/10	REVISED -

STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION

TRAFFIC SIGNAL MODERNIZATION PLAN U.S. ROUTE 12 AT WILMOT ROAD/JOHNSBURG ROAD								
	SCALE: 1"=20'	SHEET NO.	OF	SHEETS	STA.	TO STA		

	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
-	2009-128-TS	McHENRY	21	10	
		CONTRACT	#: 60	60J88	
	ILLINOIS FED. AI	D PROJECT			