

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE							
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000-2A							CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000-2A					
				80% FED.	20% STATE										80% FED.	20% STATE				
44201791	CLASS D PATCHES, TYPE II, 12 1/2 INCH	SO YD	455	455							* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	311	311					
44211796	CLASS D PATCHES, TYPE IV, 12 1/2 INCH	SO YD	33	33							* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	159	159					
20201006 21400100 40600200	GRADING AND SHAPING SHOULDERS GRADING AND SHAPING DITCHES BITUMINOUS MATERIALS (PRIME COAT)	UNIT FOOT TON	129 800 30	129 800 30							* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	246	246					
40600300	AGGREGATE (PRIME COAT)	TON	148	148							78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	197	197					
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	55	55							* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	624	624					
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1525	1525							X0322256	TEMPORARY INFORMATION SIGNING	SO FT	51.4	51.4					
40600895	CONSTRUCTING TEST STRIP	EACH	1	1																
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	447	447																
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	3624	3624																
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	36975	36975																
44201839	CLASS D PATCHES, TYPE II, 16 INCH	SO YD	43	43																
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	514	514																
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																
67100100	MOBILIZATION	L SUM	1	1																
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1																
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3841	3841																
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	436.8	436.8																
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	16017	16017																
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1163	1163																
70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	1356	1356																
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	311	311																
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	159	159																
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	427	427																
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	436.8	436.8																
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	16017	16017																
* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1163	1163																
* 78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1356	1356																

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = abruah	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>ILL 72 W/B (FORBES AVE. TO BEVERLY RD.) SUMMARY OF QUANTITIES</b>	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
Plot Scale = 50,000' / IN.	DRAWN -	REVISED -	341			32 RS-8	COOK	19	3	
Plot Date = 2/5/2010	CHECKED -	REVISED -	CONTRACT NO. 60J93							
DATE -	REVISED -	FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT								
					SCALE:	SHEET NO. OF SHEETS		STA. TO STA.		

Rev