

SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE					SUMMARY OF QUANTITIES			URBAN 100% STATE TOTAL QUANTITIES					CONSTRUCTION TYPE CODE																			
CODE NO	ITEM	UNIT	URBAN 100% STATE TOTAL QUANTITIES	ROADWAY 1000							CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 100% STATE TOTAL QUANTITIES	ROADWAY 1000																								
21101615	TOPSOIL FURNISH AND PLACE, 4"	SO YD	100	100							67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6																									
25200110	SODDING, SALT TOLERANT	SO YD	100	100							67100100	MOBILIZATION	L SUM	1	1																									
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	55	55							70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	1																									
40600300	AGGREGATE (PRIME COAT)	TON	265	265							70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1																									
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	100	100							70300100	SHORT-TERM PAVEMENT MARKING	FOOT	9300	9300																									
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2310	2310							70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2000	2000																									
40600895	CONSTRUCTING TEST STRIP	EACH	2	2							70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	22500	22500																									
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SO YD	190	190							70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	3500	3500																									
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SO YD	1800	1800							70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	200	200																									
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	115	115							70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	550	550																									
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	3	3							70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	1150	1150																									
40603595	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "F", N90	TON	6600	6600							70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	3100	3100																									
42001300	PROTECTIVE COAT	SO YD	210	210							*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	2000	2000																									
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SO YD	20	20							*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	22500	22500																									
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SO FT	50	50							*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3500	3500																									
44000159	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/2"	SO YD	13935	13935							*78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	200	200																									
44000200	DRIVEWAY PAVEMENT REMOVAL	SO YD	40	40							*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	550	550																									
44000600	SIDEWALK REMOVAL	SO FT	50	50							*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	1150	1150																									
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	1400	1400							*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	560	560																									
44002214	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3 1/2"	SO YD	575	575							78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	560	560																									
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SO YD	1400	1400							*88600600	DETECTOR LOOP REPLACEMENT	FOOT	1301	1301																									
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SO YD	250	250							X0322256	TEMPORARY INFORMATION SIGNING	SO FT	52	52																									
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SO YD	400	400							X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SO YD	9400	9400																									
55039700	STORM SEWERS TO BE CLEANED	FOOT	3900	3900							Z0004530	HOT-MIX ASPHALT DRIVEWAY PAVEMENT, 8"	SO YD	20	20																									
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	2	2							Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	130	130																									
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	2	2																																				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	20	20																																				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	5	5																																				
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	45	45																																				
60404950	FRAMES AND GRATES, TYPE 24	EACH	20	20																																				

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = kellers	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS</b> <b>DEPARTMENT OF TRANSPORTATION</b>	<b>IL ROUTE 131 (SHEELER AVE. TO SUNSET AVE.)</b> <b>SUMMARY OF QUANTITIES</b>	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
c:\pwwork\PHIDOT\KELLERS\017742\031810-stt-plan.dgn		DRAWN -	REVISED -			2711	27 RS-9	LAKE	26	3	
PLOT SCALE = 50,000' / 1" IN.		CHECKED -	REVISED -			CONTRACT NO. 60J96					
PLOT DATE = 1/28/2010		DATE -	REVISED -			FED. ROAD DIST. NO. 1 ILLINOIS FED. AID PROJECT					