

SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				SUMMARY OF QUANTITIES			100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			
CODE NO	ITEM	UNIT		URBAN 1000 LOC. 1	URBAN 1000 LOC. 2					UNIT		URBAN 1000 LOC. 1	URBAN 1000 LOC. 2		
20201006	GRADING AND SHAPING SHOULDERS	UNIT	80	80					70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	0.5	0.5	
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	35	35					70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4617	475	4142	
25200110	SODDING, SALT TOLERANT	SQ YD	35	35					70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	145.6		145.6	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	36	4	32				70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	20769	2131	18638	
40600300	AGGREGATE (PRIME COAT)	TON	176	20	156				70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1461	429	1032	
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	52.5	7	45.5				70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	369.5		369.5	
40600826	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	1875	185	1690				70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	490	92	398	
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1				70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	6170	640	5530	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	935	70	865				* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	145.6		145.6	
40600985	PORTLAND CEMENT CONCRETE SURFACE REMOVAL - BUTT JOINT	SQ YD	250		250				* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	20769	2131	18638	
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	18	18					* 78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1461	429	1032	
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	3010	375	2635				* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	369.5		369.5	
42001300	PROTECTIVE COAT	SQ YD	160	10	150				* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	490	92	398	
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	225		225				* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	300	200	100	
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SQ YD	7325	4435	2890				78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	240	200	40	
44000600	SIDEWALK REMOVAL	SQ FT	225		225				* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	93		93	
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	600	50	550				X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	51.4	51.4	
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	78.5	78.5					X4400100	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	535		535	
44201761	CLASS D PATCHES, TYPE I, 10 INCH	SQ YD	40		40				Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	60	10	50	
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	200	40	160				60406000	FRAMES AND LIDS, TYPE 1, OPEN LID	EACH	4	2	2	
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	100	25	75				60406100	FRAMES AND LIDS, TYPE 1, CLOSED LID	EACH	8	4	4	
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	50		50				X4421000	PARTIAL DEPTH PATCHING	TON	185		185	
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	4780		4780				X4422030	PARTIAL DEPTH REMOVAL 3"	SQ YD	1100		1100	
55039700	STORM SEWERS TO BE CLEANED	FOOT	600	100	500										
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	50		50										
60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	15		15										
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	1	5										
67100100	MOBILIZATION	L SUM	1	0.5	0.5										
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	0.5	0.5										
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	0.5	0.5										

*Specialty Items