

SPECIALTY ITEMS SPECIAL PROVISION	PAY ITEM NUMBER	PAY ITEM DESCRIPTION	UNITS	TOTAL QUANTITY	KEYES AVENUE QUANTITY	INDUSTRIAL DRIVE QUANTITY	MILL AVENUE QUANTITY	80% FEDERAL, 20% VILLAGE			100% VILLAGE
								1000	Y002 - TRAFFIC SIGNS	Y003 - LANDSCAPING	
Δ	60236825	INLETS, TYPE A, TYPE 11V FRAME AND GRATE	EACH	10	10	0	0	10			
Δ	60240215	INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID	EACH	1	1	0	0	1			
Δ	60240310	INLETS, TYPE B, TYPE 11 FRAME AND GRATE	EACH	3	3	0	0	3			
	60255800	MANHOLES TO BE ADJUSTED WITH NEW TYPE 1 FRAME, CLOSED LID	EACH	1	1	0	0	1			
Δ	60266600	VALVE BOXES TO BE ADJUSTED	EACH	3	3	0	0	3			
Δ	60266910	VALVE BOXES TO BE REMOVED	EACH	1	1	0	0	1			
Δ	60300310	FRAMES AND LIDS TO BE ADJUSTED (SPECIAL)	EACH	17	4	1	12	17			
	60500040	REMOVING MANHOLES	EACH	3	3	0	0	3			
	60500050	REMOVING CATCH BASINS	EACH	2	2	0	0	2			
	60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	4,647	4,245	402	0	4,647			
Δ	60623714	CONCRETE MEDIAN (SPECIAL)	SQ FT	482	482	0	0	482			
Δ	60801000	FLAP GATE (SPECIAL)	EACH	1	1	0	0	1			
Δ	61141300	STORM SEWERS, SPECIAL 36"	FOOT	712	712	0	0	712			
X	66400305	CHAIN LINK FENCE, 6'	FOOT	156	156	0	0	156			
X	66403200	CHAIN LINK GATES, 6' X 9' SINGLE	EACH	2	2	0	0	2			
	67100100	MOBILIZATION	L SUM	1	1	0	0	1			
Δ	70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1	1	0	0	1			
Δ	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	1	1	0	0	1			
	70106800	CHANGEABLE MESSAGE SIGN	CAL MO	22	14	4	4	22			
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	814	734	54	26	814			
	70300220	TEMPORARY PAVEMENT MARKING LINE 4"	FOOT	2,217	2,177	27	13	2,217			
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	271	245	18	9	271			
Δ	72000100	SIGN PANEL - TYPE 1	SQ FT	87	32	35	20	87			
	72400100	REMOVE SIGN PANEL ASSEMBLY - TYPE A	EACH	5	5	0	0	5			
X Δ	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	9.2	9.2	0.0	0.0	9			
X Δ	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	1,795	1,795	0	0	1,795			
X Δ	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	300	300	0	0	300			
X Δ	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	122	82	27	13	122			
X Δ	B2001420	TREE, CORNUS MAS (CORNELIAN CHERRY DOG WOOD), 2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	3	3	0	0	3			
X Δ	B2001620	TREE, CRATAEGUS CRUSGALLI INERMIS (THORN LESS COCKSPUR HAWTHORN), 2-1/2" CALIPER TREE FORM, BALLED AND BURLAPPED	EACH	10	10	0	0	10			
X Δ	B2006220	TREE, SYRINGA RETICULATA (JAPANESE TREE LILAC), 2-1/2" CALIPER, TREE FORM, BALLED AND BURLAPPED	EACH	38	38	0	0	38			
X Δ	X0300020	WATER SERVICE CONNECTION	EACH	8	8	0	0				8
Δ	X0301430	PRECAST CONCRETE PARKING BLOCK	EACH	6	6	0	0	6			
X Δ	X0320374	PLUG EXISTING SANITARY SEWERS	EACH	10	10	0	0	10			
X Δ	X0320591	SANITARY MANHOLES TO BE REMOVED	EACH	9	9	0	0	9			
X Δ	X0322786	SANITARY SEWER TESTING	L SUM	1	1	0	0	1			
X Δ	X0322789	TELEVISION INSPECTION OF NEW SANITARY SEWER	FOOT	1,943	1,943	0	0	1,943			
X Δ	X0323353	GATE VALVES, 10"	EACH	3	3	0	0				3
X Δ	X0323951	GATE VALVES, 4"	EACH	1	1	0	0				1
X Δ	X0324451	INSTALL WATER SERVICE COMPLETE	EACH	1	1	0	0				1
X Δ	X0325596	AIR TESTING	EACH	12	12	0	0	12			
X Δ	X0325846	ABANDONMENT OF EXISTING WATER MAINS	L SUM	1	1	0	0				1

Printed: February 8, 2010 @ 11:38 AM By: Kris Pung - Tab: 07-QUANTS (22x34)  
 COPYRIGHT © 2010 ENGINEERING ENTERPRISES, INC.

PATH: \\S01KPC01\IA0657\DWG\IA0657.DWG FINAL ENG\IA0657-COR

FILE NAME #FILE#	USER NAME = #USER# DESIGNED - JAM, SWM DRAWN - KKP CHECKED - JAM DATE - 10/16/09	REVISED - 12/02/09 REVISED - 01/22/10 REVISED - 02/03/10 REVISED - 02/08/10	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>		F.A. RTE. N/A	SECTION 06-00015-00-PV	COUNTY KANE	TOTAL SHEETS 97	SHEET NO. 7	CONTRACT NO. 63406
			PROJECT NO. HPP-1468(004)    JOB NO. C-91-175-06		SCALE: N/A    SHEET NO. 5 OF 92 SHEETS    STA. N/A    TO STA. N/A		FED. ROAD DIST. NO. - [ILLINOIS] FED. AID PROJECT				