

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	NHF			TE	NHF			
				80% FEDERAL 20% STATE 1000-2A ROADWAY	80% FEDERAL 20% STATE 1000-1A IL 26	80% FEDERAL 20% STATE Y050 FRONTAGE ROAD	80/20 FED/CITY Y046 BIKE PATH	80% FEDERAL 20% STATE X071-2A US RTE 20 OVER PECATONICA RIVER	80% FEDERAL 20% STATE X028-2A FRONTAGE ROAD OVER "WESTERN" TRIB. TO PECATONICA SN:089-2018	80% FEDERAL 20% STATE Y007 FRONTAGE ROAD OVER "EASTERN" TRIB. TO PECATONICA SN:089-2025	80% FEDERAL 20% STATE X981-2A US RTE 20 OVER JANE ADDAMS TRAIL
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	262	24		238					
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	152			152					
20101000	TEMPORARY FENCE	FOOT	465	465							
20101100	TREE TRUNK PROTECTION	EACH	70	20		50					
20200100	EARTH EXCAVATION	CU YD	518,069	445,479		72,590					
20200200	ROCK EXCAVATION	CU YD	64,405			64,405					
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	1,040	560		480					
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	36,885	36,550		335					
20400800	FURNISHED EXCAVATION	CUYD	10,651			10,651					
20600310	QUARRY RUN GRANULAR EMBANKMENT	CU YD	15,880	15,880							
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	293				165				128
20800150	TRENCH BACKFILL	CU YD	250			250					
21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	42920	26,590		16,330					
25000100	SEEDING, CLASS 1	ACRE	1.25			1.25					
25000210	SEEDING, CLASS 2A	ACRE	37.25	21.25		16.00					
25000310	SEEDING, CLASS 4	ACRE	33.50	18.25		15.25					
25000350	SEEDING, CLASS 7	ACRE	14.00	14.00							
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	6,563	4,777		1,786					
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	6,563	4,777		1,786					
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	6,563	4,777		1,786					
25000750	MOWING	ACRE	37.25	21.25		16					
25000775	SELECTIVE MOWING STAKES	EACH	1,097	596		501					
25001845	SEEDING CLASS 7 (SPECIAL)	ACRE	5.3	5.3							
25100115	MULCH, METHOD 2	ACRE	34	17		17					
25100630	EROSION CONTROL BLANKET	SQ YD	171,461	108,972		62,489					
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	36,463	26,541		9,922					
28000305	TEMPORARY DITCH CHECKS	FOOT	2,150	1,118		1,032					
28000400	PERIMETER EROSION BARRIER	FOOT	12,505	8,060		4,445					
28000500	INLET AND PIPE PROTECTION	EACH	19	7		12					
28001000	AGGREGATE (EROSION CONTROL)	TON	35	24		11					
28100105	STONE RIPRAP, CLASS A3	SQ YD	171	43		128					
28100107	STONE RIPRAP, CLASS A4	SQ YD	1,932	616		294	883	139			
28100109	STONE RIPRAP, CLASS A5	SQ YD	156			156					
28200200	FILTER FABRIC	SQ YD	2,208	736		450	883	139			

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2 (-1A, B-1, VB-1)	STEPHENSON	386	8
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
P-92-029-02			S00-01 OF 07	
CONTRACT #64799				

△ NON-PARTICIPATING ITEM (100% STATE)  
 • SPECIALITY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.P. ROUTE 301 (US RTE. 20)  
 FROM BOLTON ROAD TO WEST OF IL RTE. 26

SUMMARY OF QUANTITIES

SCALE: NONE  
 DATE: 01-22-10

DRAWN BY SJV  
 CHECKED BY RMH

