

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	NHF			TE	NHF			
				80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80/20 FED/CITY	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE	80% FEDERAL 20% STATE
				1000-2A ROADWAY	1000-1A IL 26	Y050 FRONTAGE ROAD	Y046 BIKE PATH	X071-2A US RTE 20 OVER PECATONICA RIVER	X028-2A FRONTAGE ROAD OVER "WESTERN" TRIB. TO PECATONICA SN:089-2018	Y007 FRONTAGE ROAD OVER "EASTERN" TRIB. TO PECATONICA SN:089-2025	X981-2A US RTE 20 OVER JANE ADDAMS TRAIL
28300400	AGGREGATE DITCH	TON	81	81							
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	3,042	3,042							
35100100	AGGREGATE BASE COURSE, TYPE A	TON	26,862	1,031	1,073	24,758					
35101400	AGGREGATE BASE COURSE, TYPE B	TON	5,614			2,069	3,545				
40200900	AGGREGATE SURFACE COURSE, TYPE B	CU YD	227				227				
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	61			61					
40300300	BITUMINOUS MATERIALS (COVER AND SEAL COATS)	GALLON	329				329				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	130.2	7.3	7.8	100.2	14.9				
40600300	AGGREGATE (PRIME COAT)	TON	63	8	3	52					
40603080	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N50	TON	7,376			7,376					
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	1,075		1,075						
40603310	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	2,033	287			1,746				
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4,303		358	3,945					
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	205			205					
44000100	PAVEMENT REMOVAL	SQ YD	14,869	2,072	1,392	11,405					
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	251			251					
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	3,059		1,018	2,041					
44002020	CONCRETE MEDIAN SURFACE REMOVAL	SQ FT	8,517		8,517						
44004250	PAVED SHOULDER REMOVAL	SQ YD	3,202	3,202							
48100100	AGGREGATE SHOULDERS, TYPE A	TON	4,571	359		4,212					
48203021	HOT-MIX ASPHALT SHOULDERS, 6"	SQ YD	2,562	2,562							
50102400	CONCRETE REMOVAL	CU YD	6.2							6.2	
50104400	CONCRETE HEADWALL REMOVAL	EACH	1			1					
50105220	PIPE CULVERT REMOVAL	FOOT	6	2		4					
50200100	STRUCTURE EXCAVATION	CU YD	1,220				1,020				200
50200300	COFFERDAM EXCAVATION	CU YD	204				204				
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	428					282		146	
50200500	COFFERDAMS	EACH	1				1				
50300100	FLOOR DRAINS	EACH	38				38				
50300225	CONCRETE STRUCTURES	CU YD	1,113.6				838.7			14.2	260.7
50300255	CONCRETE SUPERSTRUCTURE	CU YD	1,189.2				962.7				226.5
50300260	BRIDGE DECK GROOVING	SQ YD	3,789				3,178				611
50300265	SEAL COAT CONCRETE	CU YD	103.9				103.9				
50300280	CONCRETE ENCASEMENT	CU YD	13.4				9.2				4.2
50300300	PROTECTIVE COAT	SQ YD	4,759				3,995.0				764.0
50400805	FURNISHING AND ERECTING PRECAST PRESTRESSED CONCRETE I-BEAMS, 36 IN.	FOOT	852								852.0

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2 (-1A, B-1, VB-1)	STEPHENSON	386	9
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
P-92-029-02			SQ0-02 OF 07	
CONTRACT #64799				

△ NON-PARTICIPATING ITEM (100% STATE)
 • SPECIALITY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
 F.A.P. ROUTE 301 (US RTE. 20)
 FROM BOLTON ROAD TO WEST OF IL RTE. 26

SUMMARY OF QUANTITIES



SCALE: NONE
 DATE: 01-22-10

DRAWN BY SJV
 CHECKED BY RMH