

25000210 SEEDING, CLASS 2A					ACRE
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
466+96	RT		468+72	RT	0.11
467+56	LT		468+45	LT	0.08
477+00	RT		488+00	RT	0.92
477+00	LT		488+00	LT	0.74
488+00	RT		504+00	RT	1.34
488+00	LT		504+00	LT	1.09
504+00	RT		520+00	RT	1.34
504+00	LT		520+00	LT	0.56
520+00	RT		535+00	RT	1.26
520+00	LT		535+00	LT	1.29
535+00	RT		536+90	RT	0.14
535+00	LT		536+44	LT	0.16
544+24	RT		550+00	RT	0.49
544+24	LT		550+00	LT	0.08
550+00	RT		565+00	RT	1.26
550+00	LT		565+00	LT	0.20
565+00	RT		569+42	RT	0.39
565+00	LT		569+50	LT	0.06
570+65	RT		580+00	RT	0.79
570+25	LT		580+00	LT	0.31
579+77	LT		583+69	LT	0.06
580+00	RT		595+00	RT	1.19
580+00	LT		594+00	LT	0.77
594+00	RT		607+00	RT	1.09
594+00	LT		607+00	LT	1.34
607+00	RT		620+00	RT	1.08
607+00	LT		620+00	LT	1.05
620+00	RT		631+75	RT	0.94
620+00	LT		631+71	LT	1.14
TOTAL FOR 1000-2A ROADWAY: 21.25					
FRONTAGE ROAD					
96+00	RT		105+00	RT	0.56
96+00	LT		101+85	LT	0.63
102+18	LT		107+75	LT	0.85
105+00	RT		120+00	RT	1.13
108+20	LT		120+00	LT	1.20
120+00	RT		135+00	RT	1.11
120+00	LT		135+00	LT	1.52
135+00	RT		150+00	RT	1.37
135+00	LT		150+00	LT	1.98
150+00	RT		165+00	RT	1.79
150+00	LT		165+00	LT	1.49
165+00	RT		171+00	RT	0.38
165+00	LT		173+00	LT	0.49
182+22	LT		184+54	LT	0.13
TOTAL FOR Y050 FRONTAGE ROAD: 16.00					
TOTAL QUANTITY: 37.25					
HEINE ROAD					
8+00	RT		20+60	RT	0.75
8+00	LT		20+50	LT	0.65

25000310 SEEDING, CLASS 4					ACRE
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
467+56	LT		468+45	LT	0.18
477+00	LT		488+00	LT	2.01
488+00	LT		504+00	LT	3.09
504+00	LT		520+00	LT	1.56
520+00	LT		535+00	LT	2.67
545+00	LT		550+00	LT	0.34
550+00	LT		565+00	LT	1.10
565+00	LT		580+00	LT	1.93
579+71	LT		583+91	LT	0.47
580+00	LT		594+00	LT	1.23
582+98	LT		585+09	LT	0.19
594+00	LT		607+00	LT	0.54
607+00	LT		620+00	LT	1.81
620+00	LT		631+00	LT	1.14
TOTAL FOR 1000-2A ROADWAY: 18.25					
FRONTAGE ROAD					
96+00	LT		101+52	LT	0.34
102+50	LT		105+00	LT	0.09
105+00	LT		120+00	LT	2.74
120+00	LT		135+00	LT	2.40
123+00	RT		128+21	LT	0.19
129+89	RT		134+09	RT	1.62
135+00	LT		150+00	LT	2.47
134+09	RT		142+00	RT	0.28
142+00	RT		150+00	RT	0.87
150+00	LT		165+00	LT	3.03
150+00	RT		165+00	RT	0.29
165+00	LT		170+00	LT	0.42
165+00	RT		170+00	RT	0.04
173+00	LT		176+00	LT	0.17
178+00	LT		178+50	LT	0.06
TOTAL FOR Y050 FRONTAGE ROAD: 15.25					
TOTAL QUANTITY: 33.50					
HEINE ROAD					
13+00	LT		20+30	LT	0.13
12+00	RT		20+50	RT	0.11

25000350 SEEDING, CLASS 7					ACRE
STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
466+00	RT		472+00	C	0.21
477+00	LT		488+00	LT	1.06
488+00	LT		504+00	LT	1.54
504+00	LT		520+00	LT	1.54
520+00	LT		535+00	LT	1.45
535+00	LT		536+90	LT	0.18
544+52	LT		550+00	LT	0.53
550+00	LT		565+00	LT	1.45
565+00	LT		569+17	LT	0.40
569+17	LT		580+00	LT	0.81
580+00	LT		594+00	LT	1.46
594+00	LT		607+00	LT	1.26
607+00	LT		620+00	LT	1.25
620+00	LT		630+00	LT	0.96
TOTAL FOR 1000-2A ROADWAY: 14.00					
TOTAL QUANTITY: 14.00					
25000400 NITROGEN FERTILIZER NUTRIENT *					
POUND					
STATION		STATION		UNIT	
US20					
476+00		488+00		542	
488+00		504+00		627	
504+00		520+00		507	
520+00		535+00		581	
535+00		537+25		62	
544+50		550+00		122	
550+00		565+00		355	
565+00		569+10		119	
570+65		579+00		245	
579+00		594+00		404	
594+00		607+00		375	
607+00		620+00		462	
620+00		631+00		376	
TOTAL FOR 1000-2A ROADWAY: 4,777					
FR ROAD					
95+50		105+00		182	
105+00		120+00		337	
120+00		135+00		308	
135+00		150+00		365	
150+00		165+00		184	
165+00		175+00		163	
175+00		182+00		111	
HEINE RD	8+00	20+50		137	
TOTAL FOR Y050 FRONTAGE ROAD: 1,786					
TOTAL QUANTITY: 6,563					



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
 F.A.P. ROUTE 301 (US RTE. 20)  
 FROM BOLTON ROAD TO WEST OF IL RTE. 26  
 SCHEDULE OF QUANTITIES

SCALE: DRAWN BY AJP  
 DATE: 01-22-10 CHECKED BY RMH