F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
301	177-2 (-1A, B-1, VB-1)	STEPHENSON	386	32
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

P-92-029-02
CONTRACT #64799

SCHED-09 OF 15

54213450 END SECTIONS 15" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
TEMPORARY BIKE PARKING LOT					
5579+08.45					2
5581+87.55					2
TOTAL FOR Y046• BIKE PATH:					4
TOTAL QUANTITY:					4

54213453 END SECTIONS 18" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20					
AT WETLAND/BORROW PIT					4
TOTAL FOR 1000-2A ROADWAY:					4
FRONTAGE ROAD					
141+00.00					2
162+00.00					2
165+50.00					2
TOTAL FOR Y050 FRONTAGE ROAD:					6
TOTAL QUANTITY:					10

54213459 END SECTIONS 24" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20					
572+00.00					1
TOTAL FOR 1000-2A ROADWAY:					1
FRONTAGE ROAD					
146+00.00					2
TOTAL FOR Y050 FRONTAGE ROAD:					2
TOTAL QUANTITY:					3

54213465 END SECTIONS 30" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
96+81.51					2
TOTAL FOR Y050 FRONTAGE ROAD:					2
TOTAL QUANTITY:					2

54213471 END SECTIONS 36" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
152+00.00					1
TOTAL FOR Y050 FRONTAGE ROAD:					1
TOTAL QUANTITY:					1

54213489 END SECTIONS 54" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
HEINE ROAD					
22+06.00					2
TOTAL FOR Y050 FRONTAGE ROAD:					2
TOTAL QUANTITY:					2

54213669 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
552+00.00					1
598+25.00					1
601+50.00					1
TOTAL FOR 1000-2A ROADWAY:					3
TOTAL QUANTITY:					3

54213681 PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
528+00.00					1
629+90.94					1
TOTAL FOR 1000-2A ROADWAY:					2
TOTAL QUANTITY:					2

54214299 END SECTIONS, EQUIVALENT ROUND-SIZE 24" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
7+35.00					12
TOTAL FOR Y050 FRONTAGE ROAD:					12
TOTAL QUANTITY:					12

54214323 END SECTIONS, EQUIVALENT ROUND-SIZE 48" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
US20					
11+50.00					2
TOTAL FOR Y050 FRONTAGE ROAD:					2
TOTAL QUANTITY:					2

54215442 CAST-IN-PLACE REINFORCED CONCRETE END SECTION 42" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
129+50.00					2
TOTAL FOR Y050 FRONTAGE ROAD:					2
TOTAL QUANTITY:					2

54215991 REINFORCED CONCRETE PIPE ELBOW 36" — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
152+00.00					1
TOTAL FOR Y050 FRONTAGE ROAD:					1
TOTAL QUANTITY:					1

54248510 CONCRETE COLLAR — CU YD

STATION	OFFSET	-	STATION	OFFSET	UNIT
US 20					
572+00 LT	FOR MEDIAN DRAIN W/ CONCRETE COLLAR				0.6
629+91 LT	FOR 36" RCP EXTENSION				0.8
TOTAL FOR 1000-2A ROADWAY:					1.4
FRONTAGE ROAD					
152+00 LT	TO CONNECT ELBOW TO PIPE				0.8
TOTAL FOR Y050 FRONTAGE ROAD:					0.8
FRONTAGE ROAD OVER "EASTERN" TRIB. TO PECATONICA SN:089-2025					7.1
TOTAL QUANTITY:					9.3

550B0340 STORM SEWERS, CLASS B, TYPE 2 12" — FOOT

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE					
175+85.00	RT				86
178+25.00	RT				102
179+60.00	RT				135
TOTAL FOR Y050 FRONTAGE ROAD:					323
TOTAL QUANTITY:					323

550B0640 STORM SEWERS, CLASS B, TYPE 3 12" — FOOT

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
173+35.00	RT				98
TOTAL FOR Y050 FRONTAGE ROAD:					98
TOTAL QUANTITY:					98

60100060 CONCRETE HEADWALL FOR PIPE DRAINS — EACH

STATION	OFFSET	-	STATION	OFFSET	UNIT
FRONTAGE ROAD					
96+20	24 RT				1
98+70	24 RT				1
101+20	24 RT				1
103+70	24 RT				1
106+20	24 RT				1
108+70	24 RT				1
111+20	24 RT				1
113+70	24 RT				1
116+20	24 RT				1
118+70	24 RT				1
121+20	24 RT				1
123+70	24 RT				1
126+20	24 RT				1
128+70	24 RT				1
129+00	24 RT				1
131+50	24 RT				1
134+00	24 RT				1
136+50	24 RT				1
139+00	24 RT				1
141+50	24 RT				1
144+00	24 RT				1
146+50	24 RT				1
149+00	24 RT				1
151+50	24 RT				1
154+00	24 RT				1
155+75	24 RT				1
158+25	24 RT				1
160+75	24 RT				1
163+25	24 RT				1
165+75	24 RT				1
168+25	24 RT				1
170+75	24 RT				1
173+25	24 RT				1
175+75	24 RT				1
177+75	24 RT				1
180+25	24 RT				1
DRAIN FOR 18" SUBGRADE					
123+50	24 RT				1
126+50	24 RT				1
132+50	24 RT				1
142+00	24 RT				1
TOTAL FOR Y050 FRONTAGE ROAD:					40
TOTAL QUANTITY:					40

PARSONS BRINCKERHOFF

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.P. ROUTE 301 (US RTE. 20)
FROM BOLTON ROAD TO WEST OF IL RTE. 26

SCHEDULE OF QUANTITIES

SCALE:
DATE: 01-22-10

DRAWN BY AJP
CHECKED BY RMH